

4-060543

7-5

D-19,360

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- -

SE NE SE /4 SEC. 02, 10 S, 21 W
1650 feet from S section line
330 feet from E section line

Operator license# 5386

Lease McClellan well # 6

Operator: Production Drilling, Inc.

County Graham

Address: P.O. Box 680
Hays, Kansas 67601

Well total depth 4226 feet ^{137.34}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 175 feet

Aband. oil well , Gas well , Input well , SWD X, D & A

Plugging contractor: Co Tools License#

Address:

Company to plug at: Hour: 3:30P.M. Day: 5 Month: July Year: 94

Plugging proposal received from: Larry Patterson

Company: Production Drilling, Inc. Phone: 913-625-1182

Were: Order 275 sxs. common cement. Emergency permission to plug with rig over hole. Squeeze at 1225' w/250 sxs. Squeeze at 900' w/150 sxs. Squeeze 680' w/375 sxs. at 950#. Tubing in hole from 970' to packer set at 3771'. Lots of FES in wellbore.

Plugging Proposal Received by: Herb Deines/Don Butcher
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 4:30P.M., Day: 5, Month: July, Year: 94

Actual plugging report: 8 5/8" to 175'. 5 1/2" to 3825' w/100 sxs. Washed-over tubing to 1220' with top of tubing fish at 970'. Casing parted and shifted at 127' halting further passage with wash-over pipe and overshots. Worked tubing through interval and tagged top of fish at 970'. Pumped 100 sxs. common cement with partial loss of returns. Pulled tubing to 475' and circulated cement to surface with 175 sxs. cement. Noted partial returns until near end of plugging procedure. Pulled tubing with cement to surface. No pressures due to bad casing.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD BAD X Anhy.plug: YES Calc. NO
Bottom plug(in place): YES , CALC , NO X Dakota plug: YES X, NO
Plugged through TUBING , CASING . Elevation:

RECEIVED
STATE CORPORATION COMMISSION
7-13-1994
JUL 13 1994
CONSERVATION DIVISION
Wichita, Kansas

I did X did not observe the plugging.

[Signature]

DATE 7-26-94

DA (agent)

INV. NO. 40893

SEP 28 1994