

6 031200

X 12-8 DM
API NUMBER 15-065-02407-0001

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW NW SW, SEC. 2, T 10 S, R 21 W/E
1650 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4742

Lease Name Cooper Well # 2 SWD

Operator: Texaco Inc. for Producing
Name & Address Star Route Box 2
Russell, Ks. 67665

County Graham 139.82
Well Total Depth 4302 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 296

Abandoned Oil Well _____ Gas Well _____ ¹⁸⁸⁹ Well _____ SWD Well D&A _____

Other well as hereinafter indicated AN 18 1989 D 8197

Plugging Contractor Allied Cement Co. License Number _____

Address Russell, Ks.

Company to plug at: Hour: _____ AM Day: 8 Month: Dec Year: 19 88

Plugging proposal received from Earl Donaldson

(company name) Texaco Inc. (phone) _____

were: 8 5/8" set at 296' w/150 sks. 5 1/2" set at 3934' w/600 sks. TOC 590'.

Perf 590' w/130 sks. Shots 1780' and 980'. D.V. tool at 2312' w/1000 sks.

Order 250 sks 60/40 Poz 8% Gel 500# Hulls. Allied Cement Co. OWS Water.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:15PM Day: 8 Month: Dec Year: 19 88

ACTUAL PLUGGING REPORT Pump through tubing w/41 bbl to circulate. Laid down

tubing. Squeezed 5 1/2" w/total of 250 sks. To max psi 1000#. Close in psi 900#.

Test annulus w/0 sks to max psi 500#. Plug complete.

Remarks: Anhy
(If additional description is necessary, use BACK of this form.)

INVOICE
I (did not) observe this plugging.

DATE 1-20-89

NO. 23720

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow

12-8