

15-065-19208-0000

11-6

86
R

4-050119

TO: API number: 15- -

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW SE SE /4 SEC. 24, 10 S, 21 W
990 feet from S section line
990 feet from E section line

Operator license# 5238 Lease SCHMAHLFELDT well# 6

Operator: PETROLEUM INC. County GRAHAM

Address: 301 N. MAIN SUITE 900 Well total depth 3870 feet
WICHITA, KANSAS 67202 Conductor Pipe: _____ inch @ _____ feet
(316)291-8200 Surface Pipe: 8 5/8 inch @ 216 feet

125.77

Aband. oil well X, Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: HALLIBURTON SERVICES License# _____

Address: _____

Company to plug at: Hour: 9:00 AM Day: 6 Month: NOVEMBER Year: 1991

Plugging proposal received from: EVERETT JONES

Company: PETROLEUM INC. phone: (913)434-4647

Were: ORDER 450 SACKS 65/35 POZ-MIX 8% GEL AND 500 LBS. HULLS
WELL RECORD: 8 5/8 CSG. @ 216' WITH 150 SACKS CEMENT
5 1/2 CSG. @ 3867 WITH 75 SACKS CEMENT
PERFORATED AT 3734-3746
PORT COLLAR 1633' W/350 SACKS

Plugging Proposal Received by: MARVIN L. MILLER
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 10:30 AM, Day: 6, Month: NOVEMBER, Year: 1991

Actual plugging report: TIED ONTO 5 1/2" CASING PUMPED WITH 50 SACKS
65/35 POZ-MIX 8% GEL. SQUEEZED 5 1/2" CSG. WITH 300 SACKS CEMENT AND
500 LBS. HULLS @ 800 MAX PSI AND 250 SHUT-IN PSI. TIED ONTO BACKSIDE
SQUEEZED WITH 3 SACKS CEMENT AT 500 PSI WITH 500 SHUT-IN PSI

RECEIVED
STATE CORPORATION COMMISSION

NOV 12 1991

Remarks: _____
CONSERVATION DIVISION
Wichita, Kansas

INVOICED I did not [] observe the plugging.

Marvin L. Miller
Marvin L. Miller

DATE 12-5-91

INR. NO. 33935

John G.