

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 065 - 21,478 - 0000

NW, Sec. 24, T 10 S, R 21 WE
_____ feet from N/S section line
_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5562

Lease Name ACHESON Well # 1

Operator: LIBERTY ENTERPRISES INC.
Name & Address 308 WEST MILL SE.
PLAINVILLE, KS. 67663

County GRAHAM

Well Total Depth 3816 feet \$124.02

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 293

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor KELSO CASING PULLING License Number 6050 ^{547 → 551}

Address CHASE, KANSAS

Company to plug at: Hour: 10:30 AM Day: 20 Month: 4 Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO DON COOL

(company name) KELSO CASING PULLING (phone) _____

were: BOTTOM PLUG - PUSH 50SX COM. CEM. WITH
WIPER PLUG TO 2900 - SHOOT OFF - PULL PIPE

SAND - Com. CEM.

Signed Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 AM Day: 20 Month: 4 Year: 19 83

ACTUAL PLUGGING REPORT BOTTOM PLUG - PUSHED 50X COM. CEM AND
WIPER PLUG TO 2900.

TOP SQUEEZED WITH 35SX GEL MIXED WITH 1SX HULLS -

100SX CEMENT BLEND - 5SX GEL - 70SX CEMENT BLEND

8 5/8 WIPER PLUG RELEASED IN MIDDLE OF LAST CEMENT PLUG.

MAX. 350 PSI SHUT IN 150 PSI MAX. ~~5~~ SHUT IN 500 PSI

Remarks: 50/50 POZ 6% GEL 3% CC = CEMENT BLEND

RECOVERED 2010' OF CASING

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED

RECEIVED
STATE CORPORATION COMMISSION

Signed Carl Goodrow
(TECHNICIAN)

DATE 5-4-83

MAY 02 1983

Witness By Havel

FORM CP-2/3
Rev. 9-82

INV. NO. 4164-W

CONSERVATION DIVISION
Wichita, Kansas