

4-032298

2-24

API No. 15-065-004500000

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number 15-065-00450000  
**RECEIVED**  
**KANSAS CORP COMM**  
SW SW SE 1/4 SEC. 24, 10, 21 W  
330 feet from S section line  
2310 feet from E section line  
**3-20-98**

Operator license# 31378

Lease: Schmahlfeldt Well # 2

Operator: Universal Resources Corp.

County: Graham 122.85

Address: 44 SE 20 Road  
Great Bend, Kansas 67530

Well total depth 3780 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 192 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Express Well Service License# 6426

Address: Victoria, Kansas 67671

Company to plug at: Hour: P.M. Day: 24 Month: February Year: 1998

Plugging proposal received from: Terry Naylor

Company: Universal Resources Corporation Phone: -

Were: Order 240 sxs 60/40 pozmix - 10% gel - 500# hulls - 18 sxs gel.  
Allied Cement Company.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All , Part , None

Completed: Hour: 12:30 P.M., Day: 24 Month: February, Year: 1998

Actual plugging report: 8 5/8" set at 192' w/100 sxs cwc. 5 1/2" set at 3737' w/100 sxs.  
LKC Perfs 3591' - 3595'; 3608' - 3612'. O.H. ARB 3737' - 3780'. Squeezed 5 1/2" with 50 sxs  
cement blend with 200# hulls mixed in, followed with 18 sxs gel with 300# hulls mixed in,  
followed with 150 sxs cement blend to Max. P.S.I. 800#. Held. Squeezed 8 5/8" with 50 sxs  
cement blend to Max. P.S.I. 400#. Plug complete.

Remarks: \_\_\_\_\_

Condition of casing(in hole): GOOD  BAD  Anhy.plug: YES  NO

Bottom plug(in place): YES , CALC , NO  Dakota plug: YES , NO

Plugged through TUBING , CASING . Elevation: \_\_\_\_\_ GL

I did  / did not  observe the plugging.

Carl Goodrow  
(agent)

**INVOICED**

DATE MAR 23 1998

INV. NO. 50291