

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-02350-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 24-10S-20W
4950 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: SUTOR A Well Number: 7
County: ROOKS Total Vertical Depth: 3737 feet

Operator License No.: 6931
Op Name: BOWMAN OIL COMPANY
Address: 805 CODELL RD.
CODELL, KS 67663

Production Casing Size: 5.5 feet: 3731 100 SX CMT
Surface Casing Size: 8.625 feet: 187 150 SX CMT

8/12/05

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/12/2003 1:00 PM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: PAUL BOWMAN Company: BOWMAN OIL COMPANY Phone: (785) 434-2286

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel.
T.O.F. at 1200'.

Plugging Proposal Received By: DENNIS HAMEL WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/12/2003 5:00 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Rigged up cementers to 5 1/2" casing.
Pumped 75 sxs cement with 500# hulls down casing - locked-up to Max. P.S.I. 1500#. S.I.P. 1000#.
Pressured up 8 5/8" S.P. to 1000# - no cement pumped in annulus.

RECEIVED
OCT 30 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Dennis L. Hamel

(TECHNICIAN)

INVOICED

DATE 10-30-03

2004060694

Form CP-2/3

OCT 28 2003

BIRMINGHAM-BARTLETT

#7

SUTOR 'A'

22 24-10-20W
NW NW NE

Contr. BIRMINGHAM-BARTLETT DRLG CO.

ROOKS

County

E 2185 Comm.

Comp. 1-27-50

IP 2290 BOPD

DRAW DOWN

Tops	Depth	Datum
LANS	3432	-1247
ARB	3729	-1544
T.D.	3737	-1552

Casing

8" 187 DP 3733
 5" 3731 175' 01H/1 HR
 DD 3737
 2085' 01H/10 HRS
 SWB 20 BOPH/5 HRS

BERLAND POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS