

4-070184

15-065-01805-0000

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15- - 10/53

NE SE NW /4 SEC. 35, 10 S, 21 W  
3630 feet from S section line  
2970 feet from E section line

Operator license# 5552

Lease: Ziegler Well # 2

Operator: Gore Oil Company

County: Graham 119.37

Address: P.O. Box 2757  
Wichita, Kansas 67201-2757

Well total depth 3673 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 205 feet  
W/125 sxs.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Gore Oil License# 5552

Address: P.O. Box 2757 - Wichita, Kansas 67201-2757

Company to plug at: Hour: 4:00 P.M. Day: 1 Month: August Year: 2000

Plugging proposal received from: David R. Gordon

Company: Gore Oil Company Phone: 316-263-3535

Were: 5 1/2" set at 3672' w/100 sxs. P.B.T.D. 3635'.

L-KC Perfs 3376' - 3603'.

Squeeze 1030' with 230 sxs.

Tubing & rods sanded in at 1315'. Unable to washover.

Ordered out 250 sxs 60/40 pozmix - 10% gel with 500# hulls.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 4 2000

CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 6:00 P.M., Day: 1 Month: August Year: 2000

Actual plugging report: Ran 2 7/8" tubing to top of fish 1315'. Pulled one joint at 1285'. Allied pumped 50 sxs 60/40 pozmix - 10% gel followed with 30 sxs with 200# hulls. Cement circulated. PTOH. Allied squeezed 10 sxs with 100# hulls. Max. P.S.I. 900#. S.I.P. 800#. Hooked-up to backside of 5 1/2". Allied pumped 5 sxs. Max. P.S.I. 500#. S.I.P. 400#.

Remarks: Emergency plug orders given while rig over the hole.

Condition of casing(in hole): GOOD BAD X Any plug: YES X NO

Bottom plug(in place): YES, CALC, NO Dakota plug: YES, NO

Plugged through TUBING X, CASING. Elevation: 2106 GL

I did [ X ] / did not [ ] observe the plugging.

INVOICED  
DATE 8/10/00  
INV. NO. 1060336

Richard Willians  
(agent)