

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

15-065-22828-00-00

API NUMBER 15-065-22,8280000

LEASE NAME Grecian

WELL NUMBER 2

1,650 Ft. from S Section Line

2,310 Ft. from E Section Line

SEC. 10 TWP. 10S RGE. 22 XE or (W)

COUNTY Graham

Date Well Completed 5-7-02

Plugging Commenced 5-7-02

Plugging Completed 5-7-02

RECEIVED

MAY 17 2004
5-17-2002
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR RUSSELL OIL, INC.

ADDRESS 3535 NW 58th, STE 1060

PHONE (405) 947-9900 OPERATORS LICENSE NO. 3293

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-6-02 (date)

by Pat Staab (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.O. 3,840'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	261'	Cmtd. w/160 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each so
Push bridge plug to 1,846', pump 25 sax cement on plug thru drill pipe. Push bridge plug to 1,300', pump 100 sax cement on plug thru drill pipe. Push bridge plug to 310', pump 40 sax cement on plug thru drill pipe. Push bridge plug to 40', dump 10 sax on plug to cellar. Dump 15 sax cement down rat hole and 10 sax cement down mousehole.

Name of Plugging Contractor Shields Drilling Co. License No. 5184

Address Shields Bldg., PO Box 709, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Russell Oil, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.


Jack P. Beeman, Sec.-Treas. Contractor
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed in the same are true and correct, so help me God.

(Signature) Jack P. Beeman
(Address) Shields Bldg., Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 15th day of May, ~~2002~~ 2002

Leeth Phillips
Notary Public

My Commission Expires: _____



OR
Form 07