

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: McCoy Petroleum Corporation

Address: 8080 E. Central, Suite #300, Wichita, KS 67206-2366

Phone: 316-636-2737 x 104 Operator License # 5003

Type of Well: Gas Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 9/21/09 (Date)

by: Steve Durrant (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Kinderhook Sand Depth to Top: 4722' Bottom: 4732' T.D. 4870'
Miss Depth to Top: 4680' Bottom: 4690' T.D. 4870'
LKC Depth to Top: 4138' Bottom: 4172' T.D. 4870'

API Number 15-097-21571-0000

Lease Name: LEISS #1-13 GAS Unit A

Well Number: #1-13 PERACO PPT KCC

Spot Location (QQQQ): C SE NW

3300 Feet from North South Section Line

3300 Feet from East West Section Line

Sec 13 Twp 27 S. Rng. 18 East West

County: Kiowa

Date Well Completed: 12/22/05

Plugging Commenced: 11/21/09

Plugging Completed: 11/24/09

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Includes a RECEIVED stamp dated DEC 11 2009.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

11/21/09: Tried to blow gas off but well wouldn't die off. Pumped 60 bbls water down 4 1/2" casing to kill gas on well. Sand was at 4630. Bailed 4 sacks cement with bailer. Had 20" stretch. Ripped casing at 3240', 3010' and 2830'. Swedge in; left on tension. Ripped casing at 2610' and pipe came free. Pulled casing up to 1170' and pumped 15 gel, 50 sacks cement with 100# hulls. Pulled casing up to 390' and pumped 50 sacks cement with 100# hulls. Pulled to 40' and pumped 30 sacks cement to surface. (All cement was 60/40 Pozmix with 4% Gel).


Name of Plugging Contractor: Quality Well Service License #: 31925

Address: 190th US 56 Highway, Ellinwood, KS 67526

Name of Party Responsible for Plugging Fees: McCoy Petroleum Corporation

State of Kansas County, Sedgwick ss.

Scott Hampel - Employee of Operator (Employee of Operator) or (Operator) on above-described well, being first duty sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Scott Hampel

(Address) 8080 E. Central, Suite #300, Wichita, KS 67206-2366

SUBSCRIBED and SWORN TO before me this 10th day of December 20 09

Brent B Reinhardt My Commission Expires: 12/7/2011 Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202