

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
March 2009
**Type or Print on this Form
Form must be Signed
All blanks must be Filled**

OPERATOR: License #: 3372
 Name: Dixon Energy
 Address 1: 8100 E. 22nd St. North, Bldg. 300, Suite 200
 Address 2: _____
 City: Wichita State: KS Zip: 67226 + _____
 Contact Person: Mike Dixon
 Phone: (316) 264-9632
 Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (if needed attach another sheet)
 _____ Depth to Top: 4736 Bottom: 4476 T.D. 4812
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 007-21,551-0000
 Spot Description: _____
 N/2 SE SE SE Sec. 16 Twp. 32 S. R. 12 East West
490 Feet from North / South Line of Section
330 Feet from East / West Line of Section
 Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
 County: Barber
 Lease Name: Lonker F Well #: F-1
 Date Well Completed: _____
 The plugging proposal was approved on: 11/23/2009 (Date)
 by: Richard Lacey (KCC District Agent's Name)
 Plugging Commenced: 11/23/2009
 Plugging Completed: 11/30/2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8	407	None
		Production	4 1/2	4827	2400

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand back to 4680', spot 4 sacks cement with dump bailer, pull casing, run tubing to first 660', pump 15 sacks gel, 50 sacks 60/40 4% gel, 2nd 420', 50 sacks, 3rd 60' 20 sacks, measured 12/1 - 1' down in surface, back fill cellar

RECEIVED
DEC 11 2009
KCC WICHITA

Plugging Contractor License #: 5105 Name: Clarke Corporation
 Address 1: 107 W. Fowler Address 2: P.O. Box 187
 City: Medicine Lodge State: KS Zip: 67104 + _____
 Phone: (620) 886-5665
 Name of Party Responsible for Plugging Fees: Dixon Energy
 State of Kansas County, Barber, ss.
Mark Morgenster Employee of Operator or Operator on above-described well,
 (Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Mark Morgenster

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202