

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Charles N. Griffin
Address: P.O. Box 670, Byers, CO 80103
Phone: (620) 680-1262 Operator License #: 33936
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Steve Durrant (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-185-23498-0000
Lease Name: Curtis
Well Number: #2
Spot Location (QQQQ): _____ - _____ - E/2 - SW
1,330 Feet from North / South Section Line
2,130 Feet from East / West Section Line
Sec. 27 Twp. 22 S. R. 11 East West
County: Stafford
Date Well Completed: _____
Plugging Commenced: 10/01/09
Plugging Completed: 10/05/09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	250'	
				5 1/2"	3,646'	2,650'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand was at 3,220'; Bailed 5 sacks cement with bailer. Ripped casing at 2,810' and 2,650'. Pipe came free at 2,650'. Pulled casing up to 600'; Pumped 10 gel and 50 sacks. Pulled to 280'; Pumped 50 sacks. Pulled to 40'; Pumped 20 sacks.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925

Address: 190 US Highway 56, Ellinwood, KS 67526


Name of Party Responsible for Plugging Fees: Charles N. Griffin

State of Kansas County, Barber, ss.

Charles N. Griffin (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) _____

(Address) PO Box 127 Sawyer KS 67134



SUBSCRIBED and SWORN TO before me this 24th day of November, 2009

Notary Public

My Commission Expires: 2/25/2012

RECEIVED
DEC 11 2009
KCC WICHITA