

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-131-20173-00-01
Spot: NWNENW Sec/Twnshp/Rge: 8-4S-14E
343 feet from N Section Line, 1500 feet from W Section Line
Lease Name: MIKE MCCLAIN Well #: 1
County: NEMAHA Total Vertical Depth: 3662 feet

Operator License No.: 7775
Op Name: WILTON PETROLEUM, INC.
Address: PO BOX 391
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	276		
PROD	4.5	3659		119.02

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/08/2008 8:00 AM
Plug Co. License No.: 33695 Plug Co. Name: MID-KAN WELL SERVICE, LLC
Proposal Rcvd. from: BERNHARD RUNDSTROM Company: WILTON PETROLEUM, INC. Phone: (620) 947-3254

Proposed Plugging Method: CEMENT PLUG COVERING THE PERFORATIONS. 50' PLUG AT THE KANSAS CITY. CEMENT FROM 300' TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN WitnessType: NONE
Date/Time Plugging Completed: 10/09/2008 5:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

CIBP SET AT 3585' AND 3499'. PERFORATED THE CASING AT 1175' AND 300'.
PUMPED 20 SACKS OF CEMENT THROUGH TUBING AT 1175'. PULLED TUBING UP
TO 300' AND PUMPED 30 SACKS OF CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3570	3576	CSG	cmt

RECEIVED
KCC DISTRICT #3
NOV 19 2009 TCH
CHANUTE, KS

INVOICED
DATE 1-4-10
INV. NO. 2010060668

Remarks:

Plugged through: TBG

District: 03

Signed

Taylor C. Houser

(TECHNICIAN)

RECEIVED

NOV 23 2009

KCC WICHITA

Form CP-2/3

PKT