

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-093-20259-00-00  
Spot: SESENWNW Sec/Twnshp/Rge: 18-22S-36W  
1250 feet from N Section Line, 1100 feet from W Section Line  
Lease Name: GROPP Well #: 1  
County: KEARNY Total Vertical Depth: 3047 feet

Operator License No.: 30481  
Op Name: APOLLO ENERGIES, INC.  
Address: 10378 N 281 HWY  
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments	
CIBP		950			99.03
CIBP		2070		WITH 2 SX CMT	
SURF	8.625	305		WITH 250 SX CMT	
PROD	4.5	3045	0	WITH 180 SX CMT	

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/04/2009 10:30 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: JIM BYERS Company: ALLIED CEMENT COMPANY Phone: (620) 793-5861

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/04/2009 6:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

1ST PLUG SET CIBP @ 2070' WITH 2 SX CMT. 2ND PLUG SET CIBP @ 950'.  
PERFORATE CASING @ 925'. SET CMT RETAINER @ 888'-STRING IN WITH TBG.  
MIX & PUMP 80 SX CMT BELOW RETAINER. SHUT IN PRESSURE 600#. 3RD PLUG  
PULL OUT OF RETAINER & CIRCULATE 4 1/2" CASING WITH 65 SX CMT. 4TH  
PLUG PUMPED 110 SX CMT DOWN 8 5/8" X 4 1/2" ANNULUS. SHUT IN PRESSURE  
400#.

Perfs:

Top	Bot	Thru	Comments
2902	2974		

RECEIVED  
DEC 04 2009  
KCC WICHITA

INVOICED  
DATE 1-12-10

INV. NO. 2010060677

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED  
NOV 23 2009

KCC DODGE CITY

Signed

*Ken Jehlik*  
(TECHNICIAN)