

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-22367-00-01
Spot: NESWSESW Sec/Twnshp/Rge: 34-31S-39W
484 feet from S Section Line, 1961 feet from W Section Line
Lease Name: MLP CLOSE C Well #: 1
County: STEVENS Total Vertical Depth: 5950 feet

Operator License No.: 5447

Op Name: OXY USA INC.

Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5700		
SURF	8.625	1479		WITH 580 SX CMT
PROD	5.5	5939	1730	WITH 215 SX CMT

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 11/06/2009 11:00 AM

Plug Co. License No.: 31151

Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: DON HORTON

Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 400# HULLS & 25 SX CMT. PLUG AT 1510' WITH 50 SX CMT. PLUG AT 600' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

193.38

Plugging Proposal Received By: ERIC MACLAREN

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 11/06/2009 3:00 PM

KCC Agent: JACK MACLASKEY

Actual Plugging Report:

PUMP 400# HULLS & 25 SX CMT @ 5300'. 1ST PLUG AT 1510' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5812	5820		
5796	5802		
5748	5752		
5300	5370		

INVOICED
DATE 1-12-10
INV. NO. 2010060704

RECEIVED
DEC 07 2009
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: CSG

District: 01

Signed

Jack MacLaren
(TECHNICIAN)

RECEIVED

NOV 20 2009

KCC DODGE CITY

Form CP-2/3