

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-20863-00-00
Spot: SWSENW Sec/Twnshp/Rge: 26-25S-15W
3191 feet from S Section Line, 3320 feet from E Section Line
Lease Name: WADDLE Well #: 2
County: STAFFORD Total Vertical Depth: 4825 feet

Operator License No.: 5420
Op Name: WHITE & ELLIS DRILLING, INC.
Address: PO BOX 48848
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4350		WITH 2 SX CMT
SURF	8.625	299		WITH 225 SX CMT
PROD	4.5	4650	0	WITH 100 SX CMT

Well Type: SWD UIC Docket No: D19524.0 Date/Time to Plug: 11/18/2009 9:00 AM
Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.
Proposal Rcvd. from: DALLAS FLOWERS Company: WHITE & ELLIS DRILLING Phone: (316) 263-1102

Proposed Plugging Method: CIBP @ 4600' & 2 SX CMT. PERFORATE @ 930' & CIRCULATE CMT.

156.81

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/19/2009 11:00 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

RAN BRIDGE PLUG TO 4450' & GOT IT HUNG UP IN THE HOLE. LEFT UNSET PLUG & SETTING TOOL IN HOLE. PRESSURE TESTED CASING TRYING TO FREE UP PLUG. SET CIBP @ 4350' & PUT 2 SX CMT ON TOP OF PLUG WITH DUMP BAILER. PERFORATED 4 1/2" @ 960'. PUMPED 350 SX CMT DOWN 4 1/2" CASING. HAD CIRCULATION UP 8 5/8" X 4 1/2" ANNULUS BUT RAN OUT OF CMT. WAITED 1 HOUR FOR MORE CMT. PUMPED 45 SX CMT. NO CIRCULATION. SDON 11/19/09: TOPPED OFF 4 1/2" WITH 5 SX CMT. PUMPED 25 SX CMT DOWN 8 5/8" X 4 1/2" ANNULUS. MAXIMUM PRESSURE 400 PSIG. SHUT IN PRESSURE 300 PSIG.

Perfs:

Top	Bot	Thru	Comments
4650	4825	OH	

INVOICED
DATE 1-12-10
INV. NO. 2010060719

RECEIVED
DEC 07 2009
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED

NOV 23 2009

KCC DODGE CITY

Form CR-278

PCT