

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-113-20585-00-00  
Spot: <sup>SW</sup>~~NW~~NENE Sec/Twnshp/Rge: 26-21S-2W  
4290 feet from S Section Line, 990 feet from E Section Line  
Lease Name: BECKER Well #: 1  
County: MCPHERSON Total Vertical Depth: 3371 feet

Operator License No.: 5399  
Op Name: AMERICAN ENERGIES CORPORATION  
Address: 155 N MARKET STE 710  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	126		100 SXS CMT
PROD	5.5	3365		100 SXS CMT

109.56

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/24/2009 9:00 AM  
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION  
Proposal Rcvd. from: DOUG WARD Company: AMERICAN ENERGIES Phone: (316) 263-5785

Proposed Plugging Method: SAND TO 50' ABOVE TOP PERFS AND CAP WITH 5 SXS CEMENT. CIRCULATE TO SURFACE FROM 450'.

Plugging Proposal Received By: GREG EVES Witness Type: PARTIAL  
Date/Time Plugging Completed: 11/24/2009 11:00 AM KCC Agent: GREG EVES

Actual Plugging Report:

SANDED TO 2897' AND CAPPED WITH 5 SXS CEMENT. CUT CASING AT 535' AND PULLED. RAN 453' OF TUBING AND PUMPED 160 SXS CEMENT (LOST CIRCULATION). RETURNED NEXT DAY AND TAGGED CEMENT AT 229'. PUMPED 130 SXS TO CIRCULATE TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3365	3371		

INVOICED

DATE 1-12-10  
INV. NO. 2010060675

RECEIVED  
DEC 08 2009  
KCC WICHITA

Remarks: COPELAND CEMENTING TICKET #34409. TOTAL = 290 SXS 60/40 POZ 4% GEL

Plugged through: TBG

District: 02

Signed Greg Eves  
(TECHNICIAN)