

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-047-20221-00-00  
Spot: W2SESE Sec/Twnshp/Rge: 18-25S-16W  
660 feet from S Section Line, 990 feet from E Section Line  
Lease Name: JOHNSTON-PARKER Well #: 1  
County: EDWARDS Total Vertical Depth: 4500 feet

Operator License No.: 30481  
Op Name: APOLLO ENERGIES, INC.  
Address: 10378 N 281 HWY  
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	378		
PROD	5.5	4494	453	146.25

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/19/2009 8:00 AM  
Plug Co. License No.: 30481 Plug Co. Name: APOLLO ENERGIES, INC.  
Proposal Rcvd. from: JIM BYERS Company: APOLLO ENERGIES, INC. Phone: (620) 672-9001

Proposed Plugging Method: SPOT 200# HULLS & 50 SX COMMON CMT W/3% CC @ 3750'. PULL UP LET CMT SET & TAG. 1ST PLUG PERFORATE 5 1/2" @ 1050' & SPOT 50 SX COMMON CMT W/3% CC @ 1050'. PULL UP LET CMT SET & TAG 5 1/2". CASING PARTED @ 453'. PULL OUT OF HOLE. 2ND PLUG RUN TBG TO 400' & FILL TO SURFACE W/60/40 POZMIX 4% GEL.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/25/2009 11:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

\*\*JUNK LEFT IN BOTTOM OF HOLE: OVERSHOT @ 3785' & 600' OF 2 3/8" TBG.\*\*  
BOTTOM PLUG: SPOT 200# HULLS & 50 SX COMMON CMT W/3% CC @ 3686'  
THROUGH 2 7/8" TBG. PULL UP. LET CMT SET. RUN DOWN TO TAG. NO FILL-UP.  
SPOT 50 SX COMMON CMT W/3% CC & 100# HULLS @ 3686. PULL TBG UP. LET  
CMT SET OVERNIGHT. 11/20/09: TAG TOC @ 2990'. PERFORATE 5 1/2" @ 1050'.  
RUN TBG TO 1040' & SPOT 50 SX COMMON CMT W/3% CC. PULL TBG UP. LET  
CMT SET. TAG TOC @ 930'. LAID DOWN TBG. PREPARE TO PULL CASING. SHUT  
DOWN. 11/23/09: PULLED 453' OF 5 1/2" CASING. RUN TBG TO 420', MIX & PUMP  
10 SX GEL- 250# HULLS -150 SX CMT MIXED WITH 150# HULLS. WAIT ON CMT 4  
HOURS. TAG TOC WITH TBG @ 144'. PUMP 15 SX GEL - 150 SX POZMIX & 50 SX  
COMMON CMT. GOOD CIRCULATION BUT NO CMT AT SURFACE. WELL WAS ON  
SLIGHT VACUUM. 11/25/09: TAG TOC @ 144'. OPERATOR WAS ALLOWED TO TOP  
OFF CASING WITH 4 1/2 YDS OF REDI-MIX.

Perfs:

INVOICED  
DATE 1-12-10  
INV. NO. 2010060677

RECEIVED  
KANSAS CORPORATION COMMISSION

DEC 10 2009

CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL & COMMON CMT BY ALLIED

Plugged through: TBG

District: 01

Signed Stephen J Pfeifer  
(TECHNICIAN)

RECEIVED

DEC - 4 2009

KCC DODGE CITY

Form CP-2/3