

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-05375-00-00
Spot: NESESW Sec/Twnshp/Rge: 10-15S-14W
990 feet from S Section Line, 2970 feet from E Section Line
Lease Name: MAIER Well #: 4
County: RUSSELL Total Vertical Depth: 3222 feet

Operator License No.: 6246
Op Name: BENNETT & SCHULTE OIL CO., A GEN
Address: 140 W WICHITA AVE
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	755	0	w/250 sxs cmt
PROD	5.5	3216	0	w/500 sxs cmt <u>104.72</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/13/2009 10:30 AM
Plug Co. License No.: 32528 Plug Co. Name: FUNK, DAVID A. DBA OIL AND OPERATING SERVICES
Proposal Rcvd. from: FRANK SCHULTE Company: BENNETT & SCHULTE OIL COMPA Phone: (785) 483-2721

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 500# hulls - 11 sxs gel.
Well had low fluid level.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/13/2009 1:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Pumped on backside 500#.
Hooked up to casing - pumped 75 sxs cement with 300# hulls.
Pumped 11 sxs gel w/100# hulls.
Pumped 175 sxs cement with 100# hulls.
Max. P.S.I. 800#. S.I.P. 200#.

Perfs:

INVOICED
DATE 1-12-10
INV. NO. 2010060678

RECEIVED
DEC 07 2009
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3009.

Plugged through: CSG

District: 04

Signed Ray A Dinkel
(TECHNICIAN) CM PA

OHIO OIL

#4 MAIER

10-15-14W
NE SE SW

33

Contr. B & R DRILLING

RUSSELL

County

E 1765

Comm.


Comp. 6-25-54

IP 25 BOPD

Tops	Depth	Datum
1ST TARK	2345	-580
2ND TARK	2366	-601
TARK LM	2401	-636
WILLARD SND	2425	-660
TOP	2663	-898
HEEB	2907	-1142
LANS	2961	-1196
ARB	3217 $\frac{1}{2}$	-1452
T.D	3225	-1460

Casing
 8" 762 250 sxs
 5" 3214 500 sxs
 30
 3210

---PB 3222



INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS