

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-141-20035-00-00
Spot: SWNE Sec/Twnshp/Rge: 19-10S-15W
3300 feet from S Section Line, 1980 feet from E Section Line
Lease Name: LOCKE Well #: 1-19
County: OSBORNE Total Vertical Depth: 3679 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	215	0	w/180 sxs cmt
T1	2.375	3638		119.57
PROD	4.5	3678	0	w/150 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/19/2009 12:00 PM
Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.
Proposal Rcvd. from: BOB GRANT Company: BEREXCO, INC. Phone: (316) 265-3311

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 4% gel - 500# hulls.
Casing leaks at 2160' - 2423' - 2455'.
Lock set packer stuck at 2652' - packer at 3575' - 29 joints of tubing stuck in the hole.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/19/2009 5:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf Tech perfed at 1260' - 850' - 175'.
Berexco, Inc. RIH with tubing to 2147'.
Allied rigged to tubing and pumped 100 sxs neat - followed with 100 sxs 60/40 pozmix - 4% gel with 200# hulls mixed in to circulate cement out 4 1/2" casing.
Pulled tubing. Rigged to 4 1/2" casing with a swedge - pumped 115 sxs cement.
No pressure - well went on small vacuum.
Rigged to 8 5/8" casing - pumped 10 sxs cement.
Max. P.S.I. 500#. S.I.P. 500#.
Ran sand line 11-20-2009 - cement 48' from surface.

Perfs:

Top	Bot	Thru	Comments
3606	3612		
3598	3602		

INVOICED
DATE 1-12-10
INV. NO. 2010060679

Remarks: ALLIED CEMENTING COMPANY-TICKET #41287.

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

CM

RECEIVED

DEC 04 2009

Form CP-2/3

NOV 25 2009

KCC WICHITA

GRAHAM-MICHAELIS CORP.
 P.O. BOX 247
 WICHITA, KS.

#1-19, LOCKE
 19-10-15W
 APPX C SW NE


CONTR. RED TIGER DRG. CO.
 CITY OSBORNE

GEOL _____ FIELD WC (NATROMA EAST DISC)

R 205K CM 12/16/77 CARD ISSUED 10/5/78 P 53 BOPD @ 35% W

API 15-141-20;035

CONG SD 3598-3612



TOPS	DEPTH	DATUM
19	3679	

8-5/8" 215' 7 3/4" 3679
 MICT - PF. (CONG SD) 3598-3602,
 3606-12, AC 1000, SWB 5 BOPH/4 BRS,
 POP, STATE POT, P 53 BOPD & 35% W,
 (GR 269) TIGHT HOLE - INFO TO BE RE-
 LEASED AT A LATER DATE

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS