

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-179-21234-00-00  
Spot: NWSENE Sec/Twnshp/Rge: 3-9S-28W  
1850 feet from S Section Line, 2000 feet from W Section Line  
Lease Name: SEALOCK Well #: 1  
County: SHERIDAN Total Vertical Depth: 4033 feet

Operator License No.: 9860  
Op Name: CASTLE RESOURCES, INC.  
Address: BOX 87  
SCHOENCHEN, KS 67667

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	218	0	w/160 sxs cmt
PROD	5.5	4014	0	w/150 sxs cmt

131.07

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/10/2009 1:00 PM  
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC  
Proposal Rcvd. from: JEFF CRAWFORD Company: CASTLE RESOURCES, INC. Phone: (785) 625-5155

Proposed Plugging Method: Ordered 230 sxs 60/40 pozmix - 4% gel - 400# hulls.  
Plug through tubing and casing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/10/2009 5:00 PM KCC Agent: DARREL DIPMAN

**Actual Plugging Report:**

8 5/8" surface casing set at 218' w/160 sxs cement.  
5 1/2" production casing set at 4014' w/150 sxs cement.  
Port collar at 2292' - was not cemented.  
Non-commercial - operator elected to plug well.  
Production casing estimated to be free at 1000'.  
Set CIBP at 3790' - 2 sxs cement on top of CIBP with dump bailer.  
Perforated production casing at 2300' and 1400'.  
Ran tubing to 2400' - pumped 50 sxs cement with 100# hulls.  
Pulled tubing to 1400' - pumped 100 sxs cement with 150# hulls.  
Pulled tubing to surface.  
Cut production casing at 916'.  
Pulled casing to 280'.  
Connected to 5 1/2" production casing - pumped 80 sxs cement.  
Cement did not circulate - pulled casing to surface.  
11/11/2009 - Service unit contacted cement at 60' from surface.  
Filled casing with sand to 10' from surface - topped with 2 sxs cement.

**Perfs:**

Top	Bot	Thru	Comments
3804	3809		

INVOICED

DATE 1-12-10  
INV. NO. 2010060681

RECEIVED  
DEC 03 2009

Remarks: S.O.S. CEMENTING COMPANY-TICKET #402.

Plugged through: TBG

KCC WICHITA

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

*cm*