

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-04967-00-00
Spot: SENWNW Sec/Twnshp/Rge: 29-20S-12W
4290 feet from S Section Line, 4290 feet from E Section Line
Lease Name: KOMAREK Well #: 4
County: BARTON Total Vertical Depth: 3526 feet

Operator License No.: 5042
Op Name: EDMISTON OIL COMPANY, INC.
Address: 125 N MARKET STE 1130
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	251	0	w/unknown sxs cmt
PROD	4.5	3526	0	w/unknown sxs cmt

114.60

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/12/2009 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DALE MAY Company: EDMISTON OIL COMPANY, INC. Phone: (620) 793-2222

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel.
Emergency plug - tubing anchor stuck in casing at 60' - can pump through tubing and anchor.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/12/2009 12:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Tied onto casing - pumped 270 sxs cement - pressured to 450# P.S.I. Shut in.
Tied to backside - pumped 7 sxs cement - started coming out of head - had 100# P.S.I.

Perfs:

INVOICED
DATE 1-12-10
INV. NO. 2010060686

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN) CM

RECEIVED Form CP-2/3

DEC 04 2009

KCC WICHITA

NOV 24 2009

E K EDMISTON

#4 KOMAREK

29-20-12W 55
SE NW NW

Contr. E K EDMISTON BARTON County

E 1856 RB Comm. 11-6-61 Comp. 12-22-61 IP 25 BOPD/ARB

Tops	Depth	Datum
HEEB	3068	-1212
BR LM	3190	-1334
LANS	3206	-1350
CONG	3451	-1595
ARB	3494	-1638
TD	3526	-1670

Casing

8" 251
4" 3526

DST 3227-97/2 HRS, 80° THIN M, SPTS OIL,
BHP 13 60-1230#/30"
DST 3495-3512/2 HRS, 60° GIP, 25° O, 55°
MCO, 45° MDY OILY W, BHP 1350-1310#
DST 3512-3526/2 HRS, 50° MDY W, SPKS O,
180° W, FR O, BHP 1310-1175#
PERF 3498-3502: SH OIL: ACID 250: SWB
4½ BO/1ST HR: 3 BO/2ND HR, NW: 3800'
OIH/36 HRS: NW: ACID 750: SWB 7½ BO/1ST
HR: 11.7 BOPH/3RD HR

BATCHMANN POOL

+	+	+	+
+	+	+	+
+	+	+	+
+	+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS