

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-039-20075-00-00
Spot: NWSENE Sec/Twnshp/Rge: 36-4S-27W
3630 feet from S Section Line, 990 feet from E Section Line
Lease Name: GAUMER A 3 Well #: B-2
County: DECATUR Total Vertical Depth: 3630 feet

Operator License No.: 5042
Op Name: EDMISTON OIL COMPANY, INC.
Address: 125 N MARKET STE 1130
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7.875	263	0	150 SX
PROD	4.5	3630	0	175 SX

117.98

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/01/2009 11:00 AM
Plug Co. License No.: 31660 Plug Co. Name: ROBUCK, DON E. DBA ENERGY SEARCH OPERATING COMPANY
Proposal Rcvd. from: DALE MAY Company: EDMISTON OIL COMPANY, INC. Phone: (620) 792-6924

Proposed Plugging Method: Ordered 375 sxs 60/40 pozmix - 4% gel - 600# hulls.
Plug through tubing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/01/2009 4:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:
7 5/8" surface casing set at 240' w/263 sxs cement.
4 1/2" production casing set at 3630' w/175 sxs cement.
TD 3630'.
Perforated production casing at 2030' and 1410'.
Ran tubing to 3000' - pumped 125 sxs cement with 300# hulls.
Pulled tubing to 1700' - pumped 120 sxs cement with 300# hulls - cement to surface.
Pulled tubing to surface.
Connected to 4 1/2" production casing - pumped 30 sxs cement.
Connected to 7 5/8" surface casing - pumped 40 sxs cement.
Max. P.S.I. 200#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3531	3531		
3529	3533		
3502	3502		
3500	3504		
3453	3453		
3451	3455		
3429	3429		
3427	3431		

RECEIVED
DEC 07 2009
KCC WICHITA

Remarks: S.O.S. CEMENTING COMPANY-TICKET #411.
Plugged through: TBG

INVOICED

DATE 1-12-10
INV. NO. 2010060684

District: 04 Signed Darrel Dipman (TECHNICIAN) CM

DEC 02 2009

