

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-069-20291-00-00  
Spot: SWSWSW Sec/Twnshp/Rge: 10-29S-30W  
330 feet from S Section Line, 330 feet from W Section Line  
Lease Name: COPELAND Well #: 1-10  
County: GRAY Total Vertical Depth: 5574 feet

Operator License No.: 33785  
Op Name: ENERGY OPERATIONS KANSAS, LP  
Address: 1001 FANNIN ST, STE 3700  
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2640		WITH 2 SX CMT
CIBP		4870		WITH 2 SX CMT
CIBP		5000		WITH 2 SX CMT
SURF	8.625	1782		WITH 675 SX CMT
COND	20	42		
DVT		3176		WITH 200 SX CMT
PROD	5.5	5155	536	WITH 200 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/12/2009 2:00 PM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: SAUL Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 2640' WITH 2 SX CMT. LOAD CASING W/MUD & PULL 4 1/2" FREE PIPE. RUN TBG @ 1832' & SPOT 100 SX CMT. TAG TOC(1732' OR HIGHER). RUN TBG @ 770' & SPOT 50 SX CMT. TOP OUT 34'-4' W/10 SX CMT.

Plugging Proposal Received By: \_\_\_\_\_ Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/12/2009 4:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

\*\*SHOT CASING @ 1845' & 586'. COULD NOT PULL IT. SHOT CASING @ 536' & PULLED. THE BOTTOM JOINT OF CASING @ 536' HAD CMT ON IT FROM THE PRIMARY 2 STAGE JOB.\*\* CIBP @ 2640' WITH 2 SX CMT. RUN TBG TO 1844' & SPOT 150 SX CMT FROM 1844' TO 475'. PUMP 10 SX CMT FROM 40' TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5022	5030		4 SPF
4886	4902		3 SPF
2720	2783		3 SPF
2690	2700		

RECEIVED  
DEC 04 2009  
KCC WICHITA

INVOICED  
DATE 1-12-10  
INV. NO. 2010060687

Remarks: USED CLASS C CMT BY ORR ENTERPRISES.

Plugged through: TBG

RECEIVED

NOV 30 2009

Signed

*[Signature]*

(TECHNICIAN)

District: 01

KCC DODGE CITY