

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-055-20172-00-00  
Spot: NWSESE Sec/Twnshp/Rge: 33-22S-33W  
660 feet from S Section Line, 660 feet from E Section Line  
Lease Name: DAMME Well #: 18  
County: FINNEY Total Vertical Depth: 4550 feet

Operator License No.: 30535  
Op Name: HARTMAN OIL CO., INC.  
Address: 10500 E BERKELEY SQ PKWY STE 100  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1100		WITH 2 SX CMT
CIBP		4360		WITH 2 SX CMT
SURF	8.625	350		WITH 255 SX CMT
PROD	5.5	4550	0	WITH 150 SX CMT

147.88

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/04/2009 8:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: STAN MITCHELL Company: HARTMAN OIL Phone: (620) 277-2511

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/04/2009 10:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4360' & 2 SX CMT. CIBP @ 1100' WITH 2 SX CMT. TEST CASING TO 500# & HELD. PERFORATE @ 1075'. INJECTION RATE 2 1/2 BPM @ 500#. PUMPED 80 SX CMT, 200# HULLS & 140 SX CMT. PRESSURE TO 500#. SHUT IN PRESSURE 200#. NO BLOW OR CIRCULATION UP ANNULUS. PUMP 105 SX CMT DOWN ANNULUS @ 400#. SHUT IN PRESSURE 150#.

Perfs:

Top	Bot	Thru	Comments
4387	4391		

INVOICED  
DATE 1-12-10  
INV. NO. 2010060691

RECEIVED  
DEC 04 2009  
KCC WICHITA

Remarks: USED 60/40 POZMIZ 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

RECEIVED  
NOV 17 2009  
KCC DODGE CITY

Signed

*Ken Jehlik*  
(TECHNICIAN)