

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-113-20675-00-00  
Spot: SWSWNW Sec/Twnshp/Rge: 10-19S-2W  
2970 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: MARVIN JOHNSON Well #: 3-A  
County: MCPHERSON Total Vertical Depth: 2963 feet

Operator License No.: 5663  
Op Name: HESS OIL COMPANY  
Address: PO BOX 1009  
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	6.625	131		100 SX
PROD	4.5	2943		50 SX <b>96.30</b>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/24/2009 2:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE Phone: (620) 938-2943

Proposed Plugging Method: SAND TO 50' ABOVE TOP PERFS AND CAP WITH 4 SXS CEMENT. PUMP 35 SXS @ 450', PULL TO 250' AND CIRCULATE TO SURFACE.

Plugging Proposal Received By: GREG EVES Witness Type: PARTIAL  
Date/Time Plugging Completed: 11/24/2009 4:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

SANDED TO 2850' AND CAPPED WITH 4 SXS CEMENT. CUT CASING AT 1495' AND PULLED. RAN TUBING TO 450' AND PUMPED 35 SXS. PULLED TUBING TO 250' AND PUMPED 140 SXS TO CIRCULATE TO SURFACE.

Perfs:

INVOICED  
DATE 1-12-10  
INV. NO. 2010060692

RECEIVED  
DEC 08 2009  
KCC WICHITA

Remarks: COPELAND CEMENTING TICKET #35639. TOTAL = 175 SXS 60/40 POZ 4% GEL

Plugged through: TBG

District: 02

Signed Greg Eves (TECHNICIAN)

JK

PPT