

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-109-20871-00-00  
Spot: NESWSWSE Sec/Twnshp/Rge: 35-14S-34W  
345 feet from S Section Line, 2175 feet from E Section Line  
Lease Name: YOUNKEN RANCH Well #: 1  
County: LOGAN Total Vertical Depth: 4500 feet

Operator License No.: 33554  
Op Name: K & B NORTON OIL & INVESTMENTS,  
Address: 151 N ROCK ISLAND ST, APT 4B PO B  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	280		

146.25

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/30/2009 6:00 AM  
Plug Co. License No.: 6039 Plug Co. Name: L.D. DRILLING, INC.  
Proposal Rcvd. from: BILL Company: K&B NORTON OIL & INVESTMEN Phone: (316) 239-7782

Proposed Plugging Method: Ordered 205 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: EDWIN SCHUMACHER WitnessType: NONE  
Date/Time Plugging Completed: 11/30/2009 8:45 AM KCC Agent: EDWIN SCHUMACHER

Actual Plugging Report:  
1st. Plug at 2300' w/25 sxs.  
2nd. Plug at 1200' w/100 sxs.  
3rd. Plug at 330' w/40 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 30 sxs.

Perfs:  
**INVOICED**  
DATE 1-12-10  
INV. NO. 2010060696

Remarks: ALLIED CEMENTING COMPANY.  
Plugged through: DP

RECEIVED  
DEC 03 2009  
KCC WICHITA

ACT

District: 04 Signed Ed Schumacher (TECHNICIAN) CM

NOV 30 2009