

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-24462-00-00  
Spot: N2SEW Sec/Twnshp/Rge: 30-19S-12W  
3630 feet from S Section Line, 3300 feet from E Section Line  
Lease Name: HARRIS Well #: 8  
County: BARTON Total Vertical Depth: 3460 feet

Operator License No.: 6039  
Op Name: L.D. DRILLING, INC.  
Address: 7 SW 26TH AVE  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	302	0	225 SX
PROD	4.5	3459	324	200 SX

112.45

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/01/2009 10:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KASSELMAN Company: L.D. DRILLING, INC. Phone: (620) 793-3051

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls.  
Set up to pull casing - pulled on casing - parted 325' - pulled 325' casing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/01/2009 1:30 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Pulled 325' casing.  
Ran tubing back in to 900' - ran outside casing - stacked out - circulated cement to surface with 300 sxs cement.  
Tubing stuck in well - backed off tubing - left 870' of tubing in the well.  
Tied to surface pipe - pumped 20 sxs cement.  
Max. P.S.I. 300#. Shut in.

Perfs:

RECEIVED  
DEC 07 2009  
KCC WICHITA

INVOICED  
DATE 1-12-10  
INV. NO. 2010060697

Remarks: COPELAND ACID AND CEMENTING COMPANY-TICKET #35643.

Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

CM

Form CP-2/3

DEC 04 2009

STATE KANS COUNTY BARTON  
 FIELD FT ZARAH (LANSING/ARBUCKLE)  
 OPER MIDWAY DRLG  
 WELL 8 HARRIS  
 API 15-009-24462-0000  
 SPUD 02/04/1991  
 DTD 3460 LTD FTD ARBUCKLE

30-19S-12W  
 N2 SE NW  
 3630FSL 3300EEL SEC  
 WELL CLASS DO  
 STATUS OIL  
 COMP 02/19/1991  
 PBD 3440

+	+	+	+	+	+
+	+	+	+	+	+
+	+	+	+	+	+
+	+	+	+	+	+
+	+	+	+	+	+
+	+	+	+	+	+
+	+	+	+	+	+
+	+	+	+	+	+
+	+	+	+	+	+
+	+	+	+	+	+

LOC 2 1/2 MI E GREAT BEND, KS

Petroleum Information Corporation

IP IPP 10 BOPD GAS TSTM NO WTR GTY 40  
 PROD ZONE: PENN CONGL 3390-3400 GROSS

EL: 1830 KB 1825 GR

CSGS: 8 5/8 @ 302 W/ 225 SACKS  
 4 1/2 @ 3459 W/ 200 SACKS  
 TBGS: 2 3/8 @ 3440  
 DRLG COMP 2/11/91 RIG REL 2/11/91  
 PERFS: PENN CONGL PERF W/ 2/FT 3390-3400 GROSS  
 3390-3394 3396-3400  
 ACID 500 GALS  
 NO CORES OR DSTS

SPL TOPS:  
 OREAD 2911 -1081  
 HEEBNER 3005 -1175  
 TORONTO 3022 -1192  
 DOUGLAS 3038 -1208  
 BROWN LIME 3118 -1288  
 LANSING 3133 -1303  
 KANSAS CITY 3367 -1537  
 PENN CONGL 3378 -1548  
 ARBUCKLE 3411 -1581  
 TD 3460 -1630

NO LOGS RUN

OPER ADDRESS: BOX 1325, GREAT BEND, KS 67530

CONTR: RED TIGER DRLG GEOL: BOB PETERSEN

KS 25-050791

Copyright 1991 Petroleum Information Corporation