

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-02487-00-00
Spot: SENESEW Sec/Twnshp/Rge: 14-12S-18W
1650 feet from S Section Line, 2970 feet from E Section Line
Lease Name: JOY Well #: 4
County: ELLIS Total Vertical Depth: 3655 feet

Operator License No.: 5214
Op Name: LARIO OIL & GAS COMPANY
Address: 301 S MARKET ST
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	200	0	w/150 sxs cmt
PROD	7	3650	0	w/100 sxs cmt <u>118.79</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/18/2009 8:30 AM
Plug Co. License No.: 5214 Plug Co. Name: LARIO OIL & GAS COMPANY
Proposal Rcvd. from: DAVE JENSEN Company: LARIO OIL & GAS COMPANY Phone: (316) 265-5611

Proposed Plugging Method: Ordered 500 sxs 60/40 pozmix - 4% gel - 600# hulls - 17 sxs gel.
Tiger Wireline Service perfed at 1850' - 1410' - 840' - 150'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/18/2009 1:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Lario Oil & Gas RIH with tubing to 3130'.
Allied rigged to tubing and mixed and pumped 17 sxs gel - followed with 100 sxs 60/40 pozmix - 4% gel with 300# hulls mixed in.
Pulled tubing to 1850'. Allied rigged to tubing and pumped 140 sxs 60/40 pozmix - 4% gel with 150# hulls mixed in.
Pulled tubing to 1000'. Allied rigged to tubing and pumped 125 sxs 60/40 pozmix - 4% gel with 150# hulls to circulate cement to pit area.
Pulled tubing. Rigged to 7" casing with a swedge and pumped 55 sxs cement to circulate cement up 10" casing. Shut in 10" casing - pumped 15 sxs cement.
Max P.S.I. 200#. S.I.P. 100#.
Topped off with 4 yards cement.

Perfs:

Top	Bot	Thru	Comments
3650	3655		
3475	3487		

INVOICED
DATE 1-12-10
INV. NO. 2010060698

Remarks: ALLIED CEMENTING COMPANY-TICKET #38577.

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

RECEIVED

CM

DEC 04 2009 Form CP-2/3

KCC WICHITA

NOV 25 2009

LARIO OIL & GAS COMPANY

#4 JOY

14-12-18W
SE NE SW

Contr. _____ ELLIS _____ County

E 2141 ^{RS} Comm. _____ Comp. 7-20-56 IP 50 BOPD

Tops	Depth	Datum
TOP	31.00	- 959
HEEB	3334	-1193
TOR	3354	-1213
LANS	3378	-1237
ARB	3648	-1507
TD	3655	-1514

Casing
 10" 200 w/150 x r s
 7" 3650 w/100 x r s
 DST 3475-87/1 HR, 15' 0 SPK
 M, BHP 450#
 DST 3650-55/1 HR, 520' CL 0,
 90' MDY 0, BHP 950#
 CO 3655

WALTERS POOL

+	+	+	+
+	+	+	+
+	+	+	+
+	+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS