

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-20307-00-01  
Spot: NWSESW Sec/Twnshp/Rge: 25-9S-18W  
990 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: COMEAU OWWO Well #: 1  
County: ROOKS Total Vertical Depth: 3660 feet

Operator License No.: 8925  
Op Name: LIBERTY OPER & COMPL, INC  
Address: 308 W MILL  
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	216	0	w/140 sxs cmt
T1	2.375	3580		<u>118.95</u>
PROD	4.5	3587	0	w/125 sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/18/2009 8:00 AM  
Plug Co. License No.: 8925 Plug Co. Name: LIBERTY OPER & COMPL, INC  
Proposal Rcvd. from: ROGER COMEAU Company: LIBERTY OPER & COMPL, INC Phone: (785) 434-4686

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/18/2009 11:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Unable to get below 1415'. Casing parted - pulled bit.  
Ran 2 3/8" tubing to 1100' - stacked out - unable to get back to 1415'.  
Allied pumped 125 sxs 60/40 pozmix - 4% gel neat cement - cwc.  
Tubing stuck and backed off top joint.  
Allied tied onto 4 1/2" casing - pumped 175 sxs cement with 100# hulls.  
Max. P.S.I. 800#. S.I.P. 600#.  
Backside started circulating - cement at end of job.  
Note: Left 1050' of 2 3/8" tubing in the hole.

Perfs:

Top	Bot	Thru	Comments
3548	3550		
3526	3528		
3506	3510		
3489	3491		
3411	3413		

INVOICED  
DATE 1-12-10  
INV. NO. 2010060699

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

*Richard Williams*

(TECHNICIAN)

RECEIVED

CM

DEC 04 2009

Form CP-2/3

KCC WICHITA

NOV 25 2009

