

State of Kansas



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 12 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Russell Hoberecht of Russ Casing Pulling Inc., has this date requested permission to plug the following described well:

Mr. Hoberecht guarantees payment of the plugging fee.

Operator's full Name: Petroleum, Incorporated,

Complete Address: Garvey Building, 300 West Douglas, Wichita, Kansas.

Lease Name: Klewer Well No. B-1

Location: App:-N/2-SE-NW Sec. 24 Twp. 10 Rge. (E)(W) 21

County: Graham Total Depth 3780' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Hoberecht was instructed to plug the well as follows:

220'--8 5/8" Surface casing, cement circulated with 150 Sx.
3774'--4 1/2" Production casing cemented on bottom with 100 Sx. Top of cement @ 3360'. Open Hole completion. Well had sanding itself back thru Dakota break to 3700'.

Set 3 Sx. cement with DB @ 3700'. Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 130 Sx. cement staged.

Very truly yours,

M. L. Nichols
Conservation Division Agent