

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION

SEP 7 1972

CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Jim Lahar of B & B Drilling, Incorporated has this date requested permission to plug the following described well:Mr. Lahar guarantees payment of the plugging fee.Operator's full Name: Herndon Drilling Company,Complete Address: Box #489, Tulsa, Oklahoma.Lease Name: Holmquist Well No. 1Location: CW/2-SW-NW Sec. 11 Twp. 10 Rge. (E)(W) 22County: Graham Total Depth 3738' Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Lahar was instructed to plug the well as follows:217'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 575'.Circulate hole with heavy mud. Pull DP to 800' and displace 110 Cu. Ft. cement thru DP. Pull DP to 220' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent