

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-24947-00-00
Spot: SWSW Sec/Twnshp/Rge: 13-13S-20W
660 feet from S Section Line, 4620 feet from E Section Line
Lease Name: DREILING Well #: 1
County: ELLIS Total Vertical Depth: 3918 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	207	0	135 SX CMT
PROD	4.5	3915	0	160 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/13/2009 10:30 AM
Plug Co. License No.: 33930 Plug Co. Name: SUPER OILWELL SERVICE
Proposal Rcvd. from: DAVE FUNK Company: KANSAS CORPORATION COMMIS Phone: (785) 625-0550

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 400# hulls - 6 sxs gel.

CONTROL #20090055-001.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/13/2009 12:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfed at 2100' - 1525' - 800' - 150'.
RIH with tubing to 3014'. Rigged to tubing and pumped 6 sxs gel followed with 75 sxs 60/40 pozmix - 4% gel with 200# hulls mixed in.
Pulled tubing to 2100'. Rigged to tubing and pumped 130 sxs 60/40 pozmix - 4% gel with 200# hulls to circulate cement up 4 1/2" casing.
Pulled tubing. Rigged to 4 1/2" casing and pumped 15 sxs.
Max. P.S.I. 600#. S.I.P. 400#.
Rigged to 8 5/8" casing and pumped 20 sxs cement.
Max. P.S.I. 200#. S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3804	3808		
3734	3736		
3708	3712		
3601	3604		
0	0		

RECEIVED
JUL 15 2009
KCC WICHITA

Remarks: QUALITY OILWELL CEMENTING COMPANY-TICKET #3303.

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN)

CM

KENMARK CORP
HAYS KS 67601-0572

replacement card
WILDCAT

13-13S-20W
C SW SW

1 DREILING

site: 3/4 S & 2-1/2 E OF ELLIS KS
cont: DUKE DRILLING # 1
opd: MARK KILIAN
date: 11/20/96
spc date: 12/03/96
drig comp: 12/09/96
card issued: 05/26/97
last revised: 12/29/97
API 15-051-24947
field: WC (CALVERT EAST DISC)

ELV: 2177 KB, 2169 GL LOG	tops.....	depth/datum
ANH.....	1520	+ 657
B/ANH.....	1566	+ 611
TOP.....	3234	-1057
HEEB.....	3471	-1294
TOR.....	3493	-1316
LANS.....	3512	-1335
BKC.....	3756	-1579
MARM.....	3800	-1623
CONG.....	3850	-1673
ARB.....	3882	-1705
RTD.....	3917	-1740
LTD.....	3918	-1741

IP status:
OIL, P 1.5 BO & 60 BWP, LKC 3601-3736 OA, 01/09/97
INFO RELEASED: 12/29/97 - ADDED DSTS & SHOWS
CSG: 8-5/8" 207 / 135 SX (ALT 2), 4-1/2" 3915 / 160 SX
SHOWS: 3272 (TOP LM, PR SCAT DK DEAD STN, V SLI
ODOR), 3500 (SHAW LM, MED XLN PORO, FEW PCS
W/DK DEAD STN, NO ODOR), 3552 (LANS LM, PNPT
PORO, PSFO, SCAT SPTD STN, V SLI ODOR), 3575
(SAME AS ABOVE), 3563 (LANS LM, FEW PCS DK
TARRY STN, NSFO, SLI ODOR), 3573 (LANS LM, FSFO
IN BRKN SMPL, NO ODOR), 3580 (LANS LM, SFO),
3587 (LANS LM, SSFO), 3655 (LANS LM, FR SCAT STN,
SSFO), 3728 (LANS LM, TR SCAT STN), 3732 (SAME AS
ABOVE), 3773 (PENN LM, FNE XLN PORO, FEW PCS
SATR STN), 3890-3900 (ARB DOL, V SLI. SHW DEAD
FLK STN, NSFO, NO ODOR)

COPYRIGHT 1997
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)

KENMARK CORP
HAYS KS 67601-0572

13-13S-20W
C SW SW

1 DREILING

NO CORES

DST (1) 3786-3814 (LKC), / 45-45-45-45, 510' GIP, REC 140' CLEAN OIL, 90' MDY GSY OIL (56% OIL, 12% G, 42% M), 155' MDY GSY OIL (83% OIL, 6% G, 11% M), 30' OIL 8" GCMW (8% OIL, 5% G, 15% M, 72% W) ISIP 1008# FSIP 914# IFP 62# -104# FFP 135# -187#
DST (2) 3850-3865 (CONG), / 30-30-30-30, REC 1' M, W/SO ISIP 41# FSIP 31# IFP 31# -31# FFP 31# -31# IHP 1941# FHP 1931#
TRGT ZN: ARB (OIL), PTD 3800 (ARB), MICT - CO, PF (MARM) 3804-3808, W / 4 SPF, AC 1000 GAL (15% NE), FU 60% OIL (AMT NA), TST 21 BO/24 HRS, DECL TO NON-COMMERCIAL RAPIDLY, SD-EVAL (12/96), PF (LKC) 3734-3736, W / 2 SPF, SO, NAT, PF (LKC) 3708-3712, W / 2 SPF, AC 250 GAL (15% NE), SO, PF (LKC) 3601-3604, W / 2 SPF, AC 1250 GAL (15% NE), SO, SET 2-3/8" TBG AT 3910, NO PKR, POP, IPP 1.5 BO & 60 BWP (GR 31), 1/9/97