

1

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-00176-00-00
Spot: NENESWSW Sec/Twnshp/Rge: 9-21S-33W
1250 feet from S Section Line, 1250 feet from W Section Line
Lease Name: JONES Well #: 1
County: FINNEY Total Vertical Depth: 2661 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1200		
CIBP		2498		WITH 2 SX CMT
SURF	7	350		WITH 350 SX CMT
PROD	4.5	2651	0	

6

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/06/2009 10:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: RICHARD LACEY Company: KANSAS CORPORATION COMMIS Phone: (620) 225-8888

Proposed Plugging Method: SET CIBP @ 2500' & 2 SX CMT WITH BAILER. SET CIBP @ 1200'. PRESSURE TEST CSG TO 300 PSIG. IF CASING TESTS OUT, PERFORATE @ 1175'. PUMP 150 SX CMT DOWN 4 1/2". IF NO RETURNS, PUMP 125 SX CMT DOWN 7" X 4 1/2" ANNULUS. IF CASING DOES NOT TEST OUT, RIG UP A SINGLE DRUM RIG WITH 1200' & TBG & PACKER. FIND HOLES & PERFORATE @ 1175' IF NEEDED. RUN TBG & PACKER TO CMT THROUGH. WILL NEED 300 SX CMT ON LOCATION.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/14/2009 11:30 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

9/6/09: 1ST PLUG SET CIBP @ 2498' & 2 SX CMT. 2ND PLUG SET CIBP @ 1200'. TEST CASING TO 650#. 3RD PLUG PERFORATED 2 HOLES IN 4 1/2" @ 1175'. COULD NOT ESTABLISH RATE @ 1200#. REPERFORATE @ 1125'. ESTABLISHED RATE OF 1.5 BPM @ 1600#. 9/14/09: RE-ESTABLISH RATE @ 1.5 BPM @ 1400#. PUMPED 105 SX CMT DOWN 4 1/2" CASING. SQUEEZED ADDITIONAL 30 SX CMT OUT PERFS. SHUT IN PRESSURE 1500#. 5TH PLUG PRESSURED TESTED 7" X 4 1/2" ANNULUS TO 2500#.

Perfs:

Top	Bot	Thru	Comments
2600	2612		
2590	2595		
2564	2569		

Control #: 20090070001 (Per Ab. Well Database)

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 27 2009

Remarks: USED60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: CSG

CONSERVATION DIVISION
WICHITA, KS

District: 01

RECEIVED

OCT - 7 2009

KCC DODGE CITY

Signed

Ken Jehlik

(TECHNICIAN)

Form CR-23