

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-20232-00-01
Spot: NESW Sec/Twnshp/Rge: 28-12S-30W
1980 feet from S Section Line, 3300 feet from E Section Line
Lease Name: SCHOENDALER A OWWO Well #: 1
County: GOVE Total Vertical Depth: 4050 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	253	0	w/200 sxs cmt
PROD	4.5	4050	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/10/2009 10:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: DAVID FUNK Company: KANSAS CORPORATION COMMIS Phone: (785) 625-0550

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 500# hulls - 8 sxs gel.
Shoot perfs at 2300' and 1400'.
Control #: 200900062001 (Per Ab. Well Database)

Plugging Proposal Received By: DARREL DIPMAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/10/2009 3:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Shot perfs at 2300' and 1400'.
Ran tubing to 3900' - pumped 8 sxs gel followed with 40 sxs cement with 200# hulls.
Pulled tubing to 2275' - pumped 260 sxs cement with 300# hulls.
Pulled tubing out - tied onto backside - pumped 75 sxs cement.
S.I.P 100#.
Topped off 4 1/2" with 25 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3894	3897		

RECEIVED
AUG 17 2009
KCC WICHITA

Remarks: QUALITY CEMENTING COMPANY-TICKET #3417.

Plugged through: TBG

District: 04

Signed *Marvin Mills*
(TECHNICIAN) CM

DONALD C. SLAWSON #1 SCHOENDALER 'A' 28-12-30W
 408 120 BLDG WICHITA, KS. C. NE SW

CONTR CO. TOOLS WICHITA, KS. CTY GOVE

GEOC RALPH RUWWE FIELD WC

2771 KB 10/24/74 CARD ISSUED 11/14/74 IS D&A/MISS
 11/6/74

15-063-20,232

LOG TOPS	DEPTH	DATUM
ANH	2224	-547
HELB	3774	-1003
WOR	3801	-1030
WANS	3821	-1050
SYARK	4043	-1272
BKC	4107	-1336
WFS	4298	-1527
REW MISS	4389	-1618
STL	4414	-1643
SPERG	4468	-1697
FRD	4476	-1705
FRD	4478	-1707

8-5/8" 253/200SX
 DST (1) 3880-3897/30-45-45-60, 1006
 G.P. 270' CGO, 30' MO, N/W, 1668-3899
 BHP 1241-1226#, FP 17-69#
 DST (2) 3945-4020/30-45-30-45, 1668-3899
 W/SPOTS OF OIL, BHP 1308-1308
 FP 44-62#, 62-79#
 DST (3) 4371-4385/30-45-45-60, 20' MO
 20' VHOCM, BHP 141-114#, FP 58-
 35#, 35-44#

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS