

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-22561-00-00
Spot: SESESE Sec/Twnshp/Rge: 15-14S-13W
330 feet from S Section Line, 330 feet from E Section Line
Lease Name: DUMLER E Well #: 1
County: RUSSELL Total Vertical Depth: 2500 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	430	0	w/200 sxs cmt
PROD	4.5	2498	0	w/125 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/25/2009 9:30 AM
Plug Co. License No.: 33930 Plug Co. Name: SUPER OILWELL SERVICE
Proposal Rcvd. from: DAVE FUNK Company: KANSAS CORPORATION COMMIS Phone: (785) 625-0550

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 400# hulls.
Perf: 1430' - 780' - 380'.
CN20100021-002

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/25/2009 2:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2457' - pumped 100 sxs cement with 200# hulls mixed in.
Pulled tubing to 1225' - pumped 100 sxs cement with 200# hulls - cement circulated.
POOH. Hooked up to casing - pumped 50 sxs cement.
Circulated out the Braden head.

Perfs:

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3902.

Plugged through: TBG

RECEIVED
DEC 09 2009
KCC WICHITA

District: 04

Signed Ray A Dinkel
(TECHNICIAN) CM

YOST OIL OPERATIONS, INC.

P.O. BOX 811

RUSSELL, KS 67665

#1 'E' DUMLER

15-14-13W

SE SE SE

CONTR EMPHASIS OIL OPERATIONS

CTY RUSSELL

GEOL BLOND FARMER

FIELD HALL-GURNEY NE EXT

(1/8 NW)

+	+
+	+
+	+
+	+

ELV 1829 KB SPD 2/12/85

CARD ISSUED 5/16/85

IP P 15 BO & 200 BWPD

1824 GL

DRLG COMP 2/16/85

WAB (TARK) 2339-2377 DA

CH LOG Tops	Depth/Datum
ANH	759 + 1070
B/ANH	794 + 1035
GR HAV	2328- 499
DOVER LM	2353- 524
TARK LM	2400- 571
RTD	2500- 671

API 15-167-22,561

8 5/8 " 430 / 200SX, 4 1/2 " 2498 / 125SX
 DST (1) 2340-90 (WAB) / 30-45-30-45, GB THRU-OUT, 180' GIP,
 REC 210" SOCM, 240' W, W/SO, SIP 684-667#, FF 100-151 /
 184-276#, HP 1221-1210#
 MICT - CO, PF (TARK SD) 2339-48 & 2360-77, W / : SPF, AC
 1500G (15% MCA) & FRAC 150SX SD & 500B GEL WTR, SWB
 DWN, SD, POP, P 15 BO & 200 BWPD (GR 37%), 4/22/85

COPYRIGHT 1984
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS