

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-21976-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 15-14S-13W
2310 feet from S Section Line, 2310 feet from E Section Line
Lease Name: DUMLER G Well #: 1
County: RUSSELL Total Vertical Depth: 2468 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	237	0	w/unknown sxs cmt
PROD	4.5	2456	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/30/2009 9:30 AM
Plug Co. License No.: 33930 Plug Co. Name: SUPER OILWELL SERVICE
Proposal Rcvd. from: DAVE FUNK Company: KANSAS CORPORATION COMMIS Phone: (785) 625-0550

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 400# hulls.
Perf: 1430' - 780' - 370' - 150'.
CN20100021-001

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/30/2009 12:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report: Ran tubing to 2450' - pumped 100 sxs cement with 200# hulls mixed in.
Pulled tubing to 1250' - pumped 80 sxs cement with 200# hulls - cement circulated.
POOH. Hooked to casing - pumped 50 sxs cement.
Cement circulated out Braden head.

Perfs: _____
RECEIVED
DEC 09 2009
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3592.
Plugged through: TBG

District: 04 Signed Ray A Dinkel (TECHNICIAN) CM

DEC 04 2009

YOST OIL OPERATIONS
BOX 811

#1 "G" DUMLER

15-14-13W
NW NW SE

RUSSELL, KS 67665

CONTR BIG THREE DRILLING

CTY RUSSELL

GEOL BLOND FARMER

FIELD HALL-GURNEY

E 1842 KB CM 9/9/82 CARD ISSUED 11/24/82 IP P 15 BO & 40 BWPD

WAB (TARK) 2362-2402

API 15-167-21,976

2710
2310

+	+
+	+
+	+

LOG	Tops	Depth/Datum
SC		779 + 1063
B SC		817 + 1025
GR HAV		2353- 511
DRY SH		2361- 519
DOVER		2379- 537
LANG		2382- 540
TARK		2425- 583
RTD		2468- 626

8 5/8 " 237; 4 1/2 " 2456

NO DSTS

MICT - CO, PF (TARK) 2394-2402, 2362-72, FRAC'D (AMT NA),

POP, P 15 BO & 40 BWPD, 9/30/82

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS