

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-21581-00-00
Spot: SESWSW Sec/Twnshp/Rge: 16-14S-13W
330 feet from S Section Line, 4290 feet from E Section Line
Lease Name: DUMLER(WEST) Well #: 1
County: RUSSELL Total Vertical Depth: 2520 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	223	0	w/unknown sxs cmt
PROD	4.5	2520	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/01/2009 8:30 AM
Plug Co. License No.: 33930 Plug Co. Name: SUPER OILWELL SERVICE
Proposal Rcvd. from: DAVE FUNK Company: KANSAS CORPORATION COMMIS Phone: (785) 625-0550

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 400# hulls.
Perf: 1400' - 760' - 345' - 200'.

CN20100022-001

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/01/2009 11:00 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2500' - pumped 100 sxs cement with 200# hulls mixed in.
Pulled tubing to 1250' - pumped 85 sxs cement with 200# hulls.
Cement circulated out backside - closed in - blew on Braden head - Max. P.S.I. 600#.
POOH. Hooked up to casing - pumped 50 sxs cement.
Cement circulated out Braden head.

Perfs:

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3584.

Plugged through: TBG

RECEIVED
DEC 09 2009
KCC WICHITA

District: 04

Signed

Ray A Dinkel

(TECHNICIAN)

CM

TJW OIL OPERATIONS
BOX 347

REPLACEMENT CARD:
#1 DUMLER

16-14-13W
SE SW SW

RUSSELL, KS 67665

CONTR EMPHASIS DRILLING

CTY RUSSELL

GEOL DAN NIXON

FIELD HALL-GURNEY

1814 KB

ELV 1809 GL SPD 3/23/81

CARD ISSUED 9/3/81

IP P 5 BOPD

TARK SD - INTV NA

API 15-167-21,581

LOG Tops	Depth	Datum
ANH	758	1056
B ANH	795	1019
GR HAV	2317	503
1ST TARK SD	2328	514
DOVER	2340	526
2ND TARK SD	2349	535
TARK LM	2384	570
3RD TARK SD	2426	612
ELM LM	2453	639
RTD	2520	706

8 5 8 " 223.4 1 2 " 2520

NO DSTS
MICT - CO. PF (TARK SD) INTV NA. SWB DWN & REC WTR. W SSO.
POSSIBLE COMMUNICATION. POP, P 5 BOPD, 3:27 81 - NO OTHER
INFO RELEASED

INFO RELEASED: 11.4.82 - WAS TEMP ABD

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS