

#4

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-22317-00-00  
Spot: NWSWNW Sec/Twnshp/Rge: 5-14S-14W  
3630 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: BOXBERGER Well #: 1  
County: RUSSELL Total Vertical Depth: 3320 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S MARKET  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	261	0	w/160 sxs cmt
PROD	5.5	3314	0	w/125 sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/20/2009 10:30 AM  
Plug Co. License No.: 33930 Plug Co. Name: SUPER OILWELL SERVICE  
Proposal Rcvd. from: DAVE FUNK Company: KANSAS CORPORATION COMMIS Phone: (785) 625-0550

Proposed Plugging Method: Ordered 335 sxs 60/40 pozmix - 4% gel - 400# hulls - 10 sxs gel.  
Perf: 1550' - 800' - 425' - 140'.  
Control #: 20100008001 (Per Ab. Well Database)

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/20/2009 2:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report: \_\_\_\_\_ Perfs: \_\_\_\_\_

Ran tubing to 2900' - pumped 10 sxs gel - followed with 100 sxs cement with 400# hulls.  
Pulled tubing to 1550' - pumped 50 sxs cement.  
Pulled tubing to 800' - pumped 50 sxs cement.  
Pulled tubing to 425' - pumped 55 sxs cement - cement circulated out casing head - closed in.  
Pumped 50 sxs cement - cement circulated out the Braden head.  
POOH. Topped off casing with 20 sxs cement.

Remarks: QUALITY OIL WELL CEMENTING-TICKET #3371.  
Plugged through: TBG

RECEIVED  
AUG 27 2009  
KCC WICHITA

District: 04 Signed Ray A. Dinkel (TECHNICIAN) CM

AUG 24 2009

REPLACEMENT CARD

HUTCHINSON OIL OPERATIONS  
7TH & MAIN


#1 BOXBERGER

5-14-14W  
NW SW NW

RUSSELL, KS 67665

COUNTY EMPHASIS OIL OPERATIONS CTY RUSSELL

GEOL \_\_\_\_\_ FIELD GORHAM



ELV 1872 KB SPD 2/28/84 CARD ISSUED 5/31/84 # OIL WELL  
1867 GL DRLG COMP 3/6/84 GORHAM SD - TINTV NA  
 API 15-167-22,317

LOG	Type	Depth/Depth
SC		890+ 982
HEEB		2987-1115
DOUG		3020-1148
LANS		3041-1189
BKC		3291-1419
GORHAM SD		3314-1442
RTD		3320-1448

8 5/8 " 261 / 160 SX, 5 1/2 " 3314 / 125 SX  
 NO CORES  
 DST (1) 3285-3317 (BASAL PENN) / 30-30-0-0, REC 10' M. W /  
 GSO, ISIP 966#, IFP 58-75#  
 MICT - CO, (GORHAM SD OH), SO, POP, OIL WELL (POTENTIAL  
 NOT RPTD)

INFO RELEASED: 3/19/87 - WAS OIL WELL - TIGHT HOLE