

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-22715-00-00
Spot: NWSESW Sec/Twnshp/Rge: 29-15S-15W
990 feet from S Section Line, 3630 feet from E Section Line
Lease Name: SOLOMON DUMLER Well #: 1
County: RUSSELL Total Vertical Depth: 3475 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	613	0	w/230 sxs cmt
PROD	4.5	3448	0	w/150 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/23/2009 3:00 PM
Plug Co. License No.: 33930 Plug Co. Name: SUPER OILWELL SERVICE
Proposal Rcvd. from: DAVE FUNK Company: KANSAS CORPORATION COMMIS Phone: (785) 625-0550

Proposed Plugging Method: Ordered 310 sxs 60/40 pozmix - 4% gel - 500# hulls - 800# (8 sxs gel).
Perf at 1600' - 900' - 665' - 390'.

CN 20100041-001

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/23/2009 5:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3400' - pumped 8 sxs gel - followed with 50 sxs cement and 100# hulls.
Pulled tubing to 1650' - pumped 80 sxs cement with 200# hulls.
Cement circulated out the backside.
POOH. Hooked up and pumped 105 sxs cement.
Cement circulated out the Braden head.

Perfs:

RECEIVED
DEC 07 2009
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3012.

Plugged through: TBG

District: 04

Signed Ray A Dinkel

(TECHNICIAN)

CM

YOST OIL OPERATIONS, INC.

29-15-15W

BOX 811

SOLOMON DUMLER

NW SE SW


RUSSELL, KS 67665

CONTR EMPHASIS OIL OPERATIONS

CTY RUSSELL

GEOLOGICAL BLOND FARMER

WCC174 N OF CROMWELL
OVER 1/2 MI FROM
(PROD)



ELV 1892 KB SPD 1/15/86
1887 GL DRG COMP 1/27/86

CARD ISSUED 3/27/86
PP P 15 B0 & 25 BWRD
LKC 3191-3348 OA

LOG	Tops	Depth/Datum
ANH		964-928
B/ANH		997-895
TOP		2880-988
HEEB		3107-1215
TOR		3126-1234
LANS		3167-275
BKC		3389-1497
CONG		3422-1530
ARB		3458-1566
RTD		3475-1583
LTD		3477-1585

API 15-167-22,715

8 5/8 613/230SX-4 1/2 3448/150SX
 DST (1) 3170-3215 (LANS) / 45-45-45-45 REC 20" M. SIP 754-706# HP 40-40/40-48# HP 1685-1671#
 DST (2) 3290-3350 (LKG) / 45-45-45-45 750 GIP REC 210 OCM (35% OIL) 120 SLI GSY W & OCM (25% OIL 40% M 30% G 5% W) 90 SLI GSY W & COM (35% OIL 30% M 80% G 5% W) SIP 1032-983# HP 50-66/83-100# HP 1782-1771#
 MICT CO. RE (LKG) 3191-3202 W / 1 SRF AC 1000 GAL (20% NE) SWB DWN SO PF (LKG) 3302-3307 3318-3322 3324-3327 3338-3341 & 3346-3348 W / 2 SPF AC 2500 GAL (20% NE) SWB DWN SO RE AC 6000 GAL (20% NE & GRA) SWB OWN SO PF (LKG) 3378-3382 W / 2 SPF NON-COMMERCIAL SET 2 3/8 TBG AT 3366 POP P 15 B0 & 25 BWRD (GR 36) 2/17/86

COPYRIGHT 1985
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS