

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-21983-00-00
Spot: SWNWNWNW Sec/Twnshp/Rge: 21-15S-12W
4870 feet from S Section Line, 5080 feet from E Section Line
Lease Name: KRAUSE Well #: 3
County: RUSSELL Total Vertical Depth: 3309 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	530	0	w/250 sxs cmt
PROD	5.5	3309	0	w/125 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/10/2009 9:30 AM
Plug Co. License No.: 33930 Plug Co. Name: SUPER OILWELL SERVICE
Proposal Rcvd. from: DAVE FUNK Company: KANSAS CORPORATION COMMIS Phone: (785) 625-0550

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 600# hulls - 10 sxs gel.
Perf at 1500' - 500' - 200'.
Control Number: 20100004-003.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/10/2009 1:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3298' - pumped 10 sxs gel - 100 sxs cement with 350# hulls.
Pulled tubing to 1500' - pumped 150 sxs cement with 150# hulls.
Cement circulated out the backside - closed backside.
Pumped 90 sxs cement - circulated out the Braden Head.
POOH. Topped off with 10 sxs cement.

Perfs:

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Ray A Dinkel

(TECHNICIAN)

CM

No. _____
CORRELATION _____
WICHITA, KS

AUG 14 2009