

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-21221-00-00
Spot: E2NWNW Sec/Twnshp/Rge: 21-15S-12W
4620 feet from S Section Line, 4290 feet from E Section Line
Lease Name: KRAUSE Well #: 2
County: RUSSELL Total Vertical Depth: 3290 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	283	0	w/unknown sxs cmt
PROD	5.5	3283	0	w/100 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/19/2009 9:00 AM
Plug Co. License No.: 33930 Plug Co. Name: SUPER OILWELL SERVICE
Proposal Rcvd. from: DAVE FUNK Company: KANSAS CORPORATION COMMIS Phone: (785) 625-0550

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 600# hulls - 10 sxs gel.
Tiger Wireline Service perf at 200' - 500' - 750' - 1500'.

Control Number: 20100004-002.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/19/2009 12:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Super Oil well Service RIH with tubing to 3000'.
Quality rigged to tubing - pumped 10 sxs gel - followed with 100 sxs 60/40 pozmix - 4% gel with 300# hulls mixed in.
Pulled tubing to 1500'. Quality rigged to tubing - pumped 105 sxs cement with 300# hulls mixed in to circulate cement up 5 1/2" casing.
Shut in 5 1/2" casing - pumped an additional 50 sxs cement to circulate cement up 8 5/8" casing. Shut in 8 5/8" casing.
Pulled tubing - rigged to 5 1/2" casing with a swedge - pumped 25 sxs cement.
Max. P.S.I. 200#. S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3283	3290	OH	ARB


KANSAS CORPORATION COMMISSION
AUG 24 2009
RECEIVED

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3333.

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

CM

C.C. & S. OIL OPER.
BOX 100, RUSSELL, KS. 67665

#2 KRAUSE

21-15-12W
C E/2 NW NW

CONTR WOODMAN & IANNITTI DR.L.G. CTY RUSSELL

GEOL JIM MUSGROVE FIELD HALL-GURNEY

E 1844 KB CM 8/22/78 CARD ISSUED 5/26/79 IP OIL WELL

ARB OH 3283-90

+	+	+
+	+	+
+	+	+

API 15-167-21,221

SMP	TOPS	DEPTH	DATUM
ANH		751	+1093
HEEB		2911	-1067
TOR		2928	-1084
DOUG		2943	-1099
BR LM		2995	-1151
LANS		3008	-1164
BKC		3265	-1421
ARB		3279	-1435
RTD		3290	-1446

8-5/8" 283, 5 1/2" 3283
DST (1) 3175-3195/45-45-45-45, 75' SO
SPKD M, SIP 822-780#, FP 42-42/52-
52#
DST (2) 3262-85/45-45-45-45, 150' OCM,
SIP 323-250#, FP 52-62/73-73#
DST (3) 3283-90/30-30-30-45, 60' GIP,
165' MO, SIP 94#, FSIP INVALID,
FP 52-62#, FFP INVALID
MICT - CO, (ARB OH) TSTD, POP - OIL
WELL - POTENTIAL NOT AVAILABLE

NOTE: ORIGINAL OPERATOR WAS LAVERN
BECKER.

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS