

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20182-00-01
Spot: W2NWNW Sec/Twnshp/Rge: 21-15S-12W
4950 feet from S Section Line, 4620 feet from E Section Line
Lease Name: KRAUSE C Well #: 1
County: RUSSELL Total Vertical Depth: 3288 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	502	0	w/250 sxs cmt
PROD	5.5	3287	0	w/100 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/12/2009 8:30 AM
Plug Co. License No.: 33930 Plug Co. Name: SUPER OILWELL SERVICE
Proposal Rcvd. from: DAVE FUNK Company: KANSAS CORPORATION COMMIS Phone: (785) 625-0550

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 600# hulls - 10 sxs gel.
Perf at 200' - 500' - 750' - 1500'.

Control Number: 20100004-001

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/12/2009 11:30 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing 3000' - pumped 10 sxs gel followed with 100 sxs cement and 300# hulls.
Pulled tubing 1500' - pumped 170 sxs cement with 300# hulls.
Cement circulated out the backside. Closed backside and pumped 15 sxs cement at 500# -
no circulation out the Braden head.
POOH. Hooked up and pumped 105 sxs cement - circulated out the Braden head.
Max. P.S.I. 200#.

Perfs:

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3419.

Plugged through: TBG

District: 04

Signed

Ray Dinkel

(TECHNICIAN)

CM

RECEIVED
AUG 21 2009
KCC WICHITA
PPT

Form CP-2/3

AUG 14 2009

LEO MICHAELIS

"0" "0"

21-1E-12A

#1 KRAUSE C

A. 2 1/2 in dia

RT. #2, RUSSELL, KS.

CONTR #1- PID WELL SERVICE

CTY RUSSELL

GEOLOG

FIELD HALL-GURNEY

E 1814 KB CM 1/16/74 CARD ISSUED 2/13/75 IP P 35 BOPD + 65 BHPD
LANS 3155-64

API 15-167-20,182-A

SMP	TOPS	DEPTH	DATUM
HHY		720	+1094
HEEB		2879	-1065
TOR		2900	-1086
DOUG		2910	-1096
ERLM		2956	-1152
LANS		2978	-1164
CONG		3242	-1428
ARB		3252	-1438
TD		3272	-1458
DD TD		3288	-1474

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

OLD INFO: WAS DUKE DRLG. #1 KRAUSE "C".
SPD 3/29/68, D&A/ARB
8" 502/250SX
DST (1) 3010-60/1', 270' MW/SP OIL,
BHP 680-680#/30", FP 42-144#
DST (2) 3239-56/75", 90' OCM/S.F.G.,
BHP 782-671#/30", FP 35-64#
DST (3) 3252-61/1', 90' OCM/S.G.G.,
BHP 578-459#/30", FP 34-61#
DST (4) 3264-72/1', 140' MW, BHP 782-
714#/20", FP 35-93#

NEW INFO: WASH DOWN TO 3288 TD, SET 31"
3257-200SA; MICT - CO & PF (ARB, 207
3257-02, AC 300, SWB LD & SWB 21 BFPH
(-050), AC 1000, SWB LD & SWB 48 BFPH .42
C, POP, P 35 BFPD (100), PBTU 3133-