

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-21023-00-01
Spot: NWNENW Sec/Twnshp/Rge: 28-34S-2E
4950 feet from S Section Line, 3960 feet from E Section Line
Lease Name: CHAPMAN Well #: 1-INP
County: SUMNER Total Vertical Depth: 3600 feet

Operator License No.: 30253
Op Name: CYCLONE PETROLEUM, INCORPORAT
Address: 7030C S LEWIS ST STE 541
TULSA, OK 74136

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	254		170 SX
T1	2.375	3115		
PKR		3115		
PROD	4.5	3540	1200	150 SX

117.00

Well Type: EOR UIC Docket No: E24607.1 Date/Time to Plug: 10/21/2009 8:00 AM
Plug Co. License No.: 33277 Plug Co. Name: COOPER, ALBERT L. DBA COOPER SERVICE CO.
Proposal Revd. from: JAMES HAVER/DARREN B Company: CYCLONE PETRO Phone: (918) 291-3200

Proposed Plugging Method: SAND BACK PERFS AND CAP WITH CMT. REC. CASING. CIRC CMT FROM 300-0

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 10/21/2009 12:15 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 3100' AND CAP WITH 4 SKS OF CMT. THE CASING WAS RECOVERED FROM 1200', AND PULLED FROM THE WELLBORE. TUBING WAS RUN TOP 300', WHERE CMT WAS CIRCD TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3164	3204		


INVOICED
DATE 12-29-09
INVOICE 2010060629
RECEIVED
NOV 24 2009
KCC WICHITA

Remarks: CONSOLIDATED CMTG 60/40 4% GEL

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)