

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-20979-00-00
Spot: NWNE Sec/Twnshp/Rge: 27-23S-24W
330 feet from N Section Line, 990 feet from E Section Line
Lease Name: DON - A Well #: 3
County: HODGEMAN Total Vertical Depth: 4736 feet

Operator License No.: 5364
Op Name: BEREN CORPORATION
Address: PO BOX 20380
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	532		WITH 350 SX CMT
PROD	5.5	4728	0	WITH 700 SX CMT 153.92

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/12/2009 10:10 AM
Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.
Proposal Rcvd. from: WAYNE GERSTNER Company: BEREXCO Phone: (316) 265-3311

Proposed Plugging Method: CIBP @ 4700' OR 100# HULLS & 25 SX CMT. GEL TO 1680'. TIH CIRCULATE 5 1/2" TO SURFACE WITH CMT. CHECK BACKSIDE.

Plugging Proposal Received By: JACK MACLASKEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/12/2009 1:50 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

PUMP 32 SX GEL, 100# HULLS, & 25 SX CMT @ 4726'. AT 1688' CIRCULATED CMT TO SURFACE WITH 165 SX CMT. PUMPED 20 SX CMT DOWN 5 1/2" X 8 5/8" ANNULUS. PRESSURED TO 500#. TOPPED OFF 5 1/2" WITH 20 SX CMT.

Perfs:

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 23 2009

CONSERVATION DIVISION
WICHITA, KS

INVOICED
DATE: 12.29.09
INV NO. 2010060624

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed Eric McClaren
(TECHNICIAN)

RECEIVED

NOV 17 2009

KCC DODGE CITY

Form CP-2/3