

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-01899-00-00
Spot: SESENW Sec/Twnshp/Rge: 6-10S-25W
2970 feet from S Section Line, 2970 feet from E Section Line
Lease Name: GRA-SHER Well #: GA-1
County: GRAHAM Total Vertical Depth: 4044 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	204	0	125 SX
PROD	5.5	4038	0	500 GALLONS LATEX

131.43

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/04/2009 9:00 AM
Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 500# hulls.
Plug through tubing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/04/2009 1:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 204' w/125 sxs cement.
5 1/2" production casing set at 4038' w/500 gallons latex.
CIBP at 4020'.
Perforated production casing at 2200' and 1350'.
Ran tubing to 3200' - pumped 150 sxs cement with 300# hulls.
Pulled tubing to 2400' - pumped 125 sxs cement with 100# hulls - cement to surface.
Pulled tubing to surface.
Connected to production casing - pumped 145 sxs cement.
Max. P.S.I. 500#. S.I.P. 200#.
Connected to 8 5/8" surface casing - pumped 30 sxs cement.
Max. P.S.I. 250#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
4038	4044		
4000	4003		
3970	3972		
3906	3908		
3506	3508		W/ 100 SAKS

INVOICED
DATE: 12.29.09
TW NO. 2010060625

Remarks: ORIGINALLY KNOWN AS GAYLORD #1. ALLIED CEMENTING COMPANY-TICKET #33641.

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

CM

NOV 16 2009

RECEIVED
Form CP-2/3
NOV 30 2009
KCC WICHITA

KIMBARK EXPLORATION CO #1 GAYLORD

6-10-25W
SE SE NW

Contr. KIMBARK EXPL

GRAHAM County

E. 2578RB Comm. 6-28-59 Comp. 8-21-59 IP

99 BOPD
PHY POT

Tops	Depth	Datum
HEEB	3798	-1220
TOR	3820	-1242
KC	3830	-1252
TD	4039	-1461

Casing
 8" 205
 5" 4039
 DD 4013: NS: PB: PERF 4000-03:
 ACID 500: WTR: PB 3990: PERF 3770-
 72: WTR: PB 3950: PERF 3905-08:
 ACID 500: 3000' WIH: SQZ: PERF
 20/3906-08: ACID 500: SWB 5 BOPH:
 ACID 2500: 10 BOPH/4 HR

GRA-SHER POOL

+	+	+	+
+	+	+	+
+	+	+	+
+	+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS