

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-00274-00-01
Spot: SWNWSE Sec/Twnshp/Rge: 22-19S-8W
1686 feet from S Section Line, 2437 feet from E Section Line
Lease Name: JOHNSTON Well #: 1
County: RICE Total Vertical Depth: 3300 feet

Operator License No.: 6166
Op Name: CHEW, BILL, INC.
Address: 621B CRAZY HORSE RD
HUTCHINSON, KS 67502

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	196		
PROD	4.5	3298	1400	115 SX CMT <u>107.25</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/14/2009 8:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE INC Phone: (620) 562-8088

Proposed Plugging Method: SAND 50' OVER PERFS AND CAP WITH 4 SX'S CEMENT, CUT CASING AND PULL TO 1150' AND PUMP 35 SK'S CEMENT, PULL CASING TO 750' AND PUMP 35 SX'S, PULL CASING TO 250' AND CIRCULATE CEMENT TO SURFACE.

Plugging Proposal Received By: GREG EVES Witness Type: NONE
Date/Time Plugging Completed: 11/14/2009 11:30 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU ON 11-12-09, CK BOTTOM. SAND PERFS TO 3150' AND CAP WITH 4 SX'S CEMENT. ATTEMPTED CUTTING THE CASING THRU MOST OF DAY ON 11-13-2009. CUT CASING AT 1400' ON 11-14-2009, AND PULL TO 1150' AND PUMP 35 SX'S CEMENT WITH THIXOTROPIC ADDITIVE. PULL CASING TO 750'. LET SET FOR APPROX 1 HR--TAG AT 1000'. PUMP 35 SX'S CEMENT AT 750'. PULL CASING TO 250' AND CIRCULATE CEMENT TO SURFACE. PULL CASING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3224	3228	CSG	
3210	3216	CSG	

INVOICED
DATE 12-29-09
INV. NO. 2010060624

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 23 2009

CONSERVATION DIVISION
WICHITA, KS

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET #C-35632. USED 180 SX'S TOTAL. (*THIXOTROPIC ADDITIVE HARDENS CEMENT FASTER).

Plugged through: CSG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)