

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-23313-00-00
Spot: S W N W N W
Sec/Twnshp/Rge: 21-26S-5E
3965 feet from S Section Line, 4881 feet from E Section Line
Lease Name: EAST KOOGLER Well #: E3
County: BUTLER Total Vertical Depth: 2579 feet

Operator License No.: 32979
Op Name: DUNNE INVESTMENTS OPERATING, I
Address: 8100 E 22ND ST N # 1100
WICHITA, KS 67226

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| CIBP | | 2560 | | W/ 2 SX |
| SURF | 8.625 | 200 | | 150 SX |
| PROD | 4.5 | 2578 | | 50 SX |

63.82

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/13/2009 8:00 AM
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: GARY LARUE Company: DUNNE INVESTMENTS OPERATING, INC. Phone: (316) 684-6508

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: NONE
Date/Time Plugging Completed: 08/13/2009 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2471', CONSOLIDATED MIXED & PUMPED 40 SXS CLASS A COMMON 4% CC AND DISPLACED IN CASING. LAYED DOWN TUBING. TAGGED CEMENT @ 1888'. PRESSURED CASING, HELD OK. SHOT SQUEEZE HOLES @ 280', CONSOLIDATED ESTABLISHED CIRCULATION & MIXED & PUMPED 188 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00, 8-13-2009, CONSOLIDATED CEMENT TICKET #21280.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|------------|
| 2478 | 2480 | | W/ 2 SHOTS |

INVOICED
DATE: 12-29-09
INV NO: 2010060631

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 23 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: TBG

District: 02

Signed

Duane Krueger

(TECHNICIAN)

14

PKS