

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-069-20294-00-00
Spot: NENESW Sec/Twnshp/Rge: 10-29S-30W
2310 feet from S Section Line, 2310 feet from W Section Line
Lease Name: COPELAND Well #: 2-10
County: GRAY Total Vertical Depth: 5622 feet

Operator License No.: 33785
Op Name: ENERGY OPERATIONS KANSAS, LP
Address: 1001 FANNIN ST, STE 3700
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4638		WITH 2 SX CMT
CIBP		4808		WITH 2 SX CMT
SURF	9.625	1710		WITH 470 SX CMT
COND	20	40		
PROD	5.5	5622	933	WITH 515 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 11/17/2009 10:05 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 4638', PLUS 2 SKS CEMENT. LOAD CSG W/MUD & PULL 4 1/2" FREE PIPE. RUN TBG @ 1760', SPOT 100 SKS CEMENT. TAG TOC (1660' OR HIGHER). SPOT 50 SKS 770'-670'. TOP OUT 34'-4' W/ 10 SKS CEMENT

182.72

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/17/2009 11:25 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4638' WITH 2 SX CMT. LOAD HOLE WITH 40 BBL MUD. 1ST PLUG AT 1750' WITH 100 SX CMT. 2ND PLUG AT 770' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5286	5340		3 SPF
4688	4698		3 SPF

INVOICED
DATE: 12-29-09
INV. NO. 2010060632

RECEIVED
NOV 30 2009

KCC WICHITA

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

RECEIVED

NOV 20 2009

KCC DODGE CITY

Signed

Eric MacLaren

(TECHNICIAN)