

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-21882-00-00
Spot: S2SWNESW Sec/Twnshp/Rge: 4-33S-39W
1360 feet from S Section Line, 1650 feet from W Section Line
Lease Name: DEGARMO TRUST Well #: 4 #1
County: MORTON Total Vertical Depth: 6417 feet

Operator License No.: 5278
Op Name: EOG RESOURCES, INC.
Address: 3817 NW EXPRESSWAY STE 500
OKLAHOMA CITY, OK 73112

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1618		WITH 500 SX CMT

208.55

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/14/2009 9:00 AM
Plug Co. License No.: 34000 Plug Co. Name: KENAI MID-CONTINENT, INC.
Proposal Rcvd. from: PRESTON Company: EOG RESOURCES Phone: (405) 246-3100

Proposed Plugging Method: 1ST PLUG AT 1650' WITH 50 SX CMT. 2ND PLUG AT 630' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: JACK MACLASKEY Witness Type: NONE
Date/Time Plugging Completed: 11/14/2009 11:00 AM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

1ST PLUG AT 1659' WITH 100 SX CMT. 2ND PLUG AT 627' WITH 50 SX CMT. 3RD PLUG AT 62' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

RECEIVED
NOV 25 2009
KCC WICHITA

INVOICED
DATE 12-29-09
INV. NO. 2010060633

Remarks: USED 60/40 POZMIX 4% GEL BY HALLIBURTON.

Plugged through: DP

District: 01

RECEIVED

NOV 17 2009

KCC DODGE CITY

Signed

Jack MacLaskey
(TECHNICIAN)

Form CP-100