

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-22176-00-00
Spot: SWSW Sec/Twnshp/Rge: 7-16S-27W
800 feet from S Section Line, 330 feet from W Section Line
Lease Name: FROELICH TRUST Well #: 14-7
County: LANE Total Vertical Depth: 4550 feet

Operator License No.: 34038
Op Name: FLATIRONS RESOURCES LLC
Address: 303 E 17TH AVE STE 940
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	220		WITH 150 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/19/2009 4:30 AM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: KIRBY Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: 1ST PLUG AT 2040' WITH 50 SX CMT. 2ND PLUG AT 1350' WITH 80 SX CMT. 3RD PLUG AT 690' WITH 50 SX CMT. 4TH PLUG AT 240' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

147.88

Plugging Proposal Received By: LINDLEY REIMER Witness Type: NONE
Date/Time Plugging Completed: 11/19/2009 6:30 AM KCC Agent: LINDLEY REIMER

Actual Plugging Report:

1ST PLUG AT 2040' WITH 50 SX CMT. 2ND PLUG AT 1350' WITH 80 SX CMT. 3RD PLUG AT 690' WITH 50 SX CMT. 4TH PLUG AT 240' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Perfs:

NOV 29 2009
DATE: 12.29.09
TV TO: 2010060634

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY QUALITY OIL WELL CEMENTING.

Plugged through: DP

District: 01

Signed _____

[Signature]
(TECHNICIAN)

RECEIVED
NOV 24 2009
KCC DODGE CITY

RECEIVED
NOV 30 2009

KCC WICHITA